



00054536

## DAILY REPORT DETAILED

RECEIVED

AUG 25 1975

COLO. OIL &amp; GAS CONS. COMM.

LEASE Gebauer "A"

WELL NO. 1

SHEET NO.

DATE TOTAL  
NATURE OF WORK DEPTH  
PERFORMED

1975  
March  
12

GERAUER "A" NO. 1 PSTD 4911. /INITIAL REPORT/. WASHING OVER FISH. 3/5/75 - MI RANEY WS TO PULL RODS, PUMP, TBG AND PERFORATE UPPER PORTION OF ZONE. PULLED 3250 FT 3/4 IN. ROES TO BREAK IN BOX. PU TO PULL TBG, SHOT FL, FL AT 500 FT. 3/6/75 - FOUND TBG STUCK, PU HOWCO. PMPD IN ANNULUS 3 BPM AT 800 LB. PMPD 500 GALS 15 PERCENT HCL. DISPLACED W/40 BW, MOVED ACID SLOWLY ACROSS PERFS WITH NO RELIEF IN PRESS. 3/7/75 - RAN 1-1/4 IN. POLISH ROD FISHING TOOL, FISHED RODS AND PMP, SWBD TBG DRY, FILLED TBG W/WTR. PRESS TO 2500 LB. SDON. 3/8/75 - SWBD TBG DN, SPTD 500 GALS 15 PERCENT. PRESS TO 2500 LB, MOVED VEPY SLOW, PRESS BROKE, CIRC TO SURFACE, ACID TO SURFACE AT 74 BBLs PMPD, CIRC UNTIL FRESH WTR TO SURFACE, TBG WOULD NOT MOVE. RAN MCCULLOUGH FREE POINT, FOUND TBG STUCK AT 4835 FT RKB. CUT OFF TBG AT 4828 FT W/MCCULLOUGH CHEMICAL CUTTER, LEFT 15 FT JT 2-3/8 IN. TBG, 31 FT JT 2-3/8 IN. PERF NIPPLE, AND MUD ANCHOR IN HOLE. 3/10/75 - PULLED 4821 FT TBG, FOUND SPLIT JT AT 3450 FT, W/ W/OS AND HYD JARS, JARRED TO 60,000 LB, WOULD NOT COME LOOSE. COOH W/FISHING TOOLS. 3/11/75 - W/ W/3-3/4 IN. WASHOVER PIPE, WASHING OVER FISH AT 4828 FT. LOCATION - 1983 FT FSL AND 1989 FT FEL, NW SE, SEC. 28-T2N-R54W, WASHINGTON CO., COLORADO. RUBY FIELD. ELEV. 4550 FT KB. SUB AREA CODE 674. WELL HAS BEEN SHUT-IN SINCE PHILLIPS ACQUIRED MARCH 1, 1970. PREVIOUS TEST NOT AVAILABLE..

APR 1975  
CO

13

GERAUER A NO. 1 PSTD 4911. COOH W/TBG FISH. WASHED OVER FISH TO 4911 FT. COOH W/WASH PIPE. W/ W/OS, LATCHED ON FISH. STARTED COOH W/FISH, 60 JTS OUT. SDON..

14

GERAUER A NO. 1 PSTD 4911. PREP TO ACIDIZE. REC ALL FISH. W/ W/TBG AND PKR TO SWAB, SWBD DRY..

15-17

GERAUER A NO. 1 PTD 4911. PREP TO LD TBG AND RELEASE WS UNIT PENDING APPROVAL TO P AND A. 3/15/75 600 FT FILLUP OVERNIGHT, SWBD 1 HR, REC/D 3 BBL. MUDDY WTR. RU HOWCO, PMPD 500 GAL 15 PERCENT HCL INTO PERFS AT 4843-4846, DISPLACED W/20 BBL WTR. AIR 1 BPM, MP 60 LB, ISDP 0 LB. 20 BBL LW AND 12 BBL LA TO RECOVER. SWBD 20 BLW AND 12 BLAW AND 5 BFW. LAST 6 RUNS SWBD EVERY 30 MIN. AND FOUND 200 FT FILLUP EACH RUN. SDON. 3/16/75 COOH W/TBG AND PKR. RU SCH., W/ W/3-3/8 IN. CSG GUN, GUN STOPPED AT 2263 FT, PL/D 3000 LB TO FREE, W/ W/SWAB STEM AND JARS, STOPPED AT 1800 FT, COOH W/SWAB STEM AND JARS. SDON..

18

GERAUER "A" NO. 1 PTD 4911. LD TBG FROM DERRICK. RELEASED RIG 2/00 P.M. 3/17/75. TEMP. DROPPED FROM REPORT PENDING APPROVAL TO P AND A..

*File*