

Company KINGWOOD OIL COMPANY Formations "D" SAND Page 1 of 1  
Well DONALD J. TUTTLE NO. 2 Core DIAMOND CONVENTIONAL File RP-2-2232  
RUBY Drilling Fluid WATER BASE MUD Date Report 11-1-59  
County WASHINGTON State COLORADO Elevation 4530 KB Analysts DI  
Location C NW NE 28 2N 54W Remarks SERVICE NO. 8



# CORE ANALYSIS RESULTS

(Figures in parentheses refer to footnote remarks)

DEPTH FEET	PERMEABILITY MILLIDARIES	WATER CONTENT %	WATER CONTENT %	WATER CONTENT %	WATER CONTENT %	REMARKS
1 4809-10	36 ✓	6.4	19.9 ✓	1.0	46.9 (2)	Sandstone, Fine-Grain, Thin Carbonaceous Partings.
2 4810-11	53 ✓	45	19.7 ✓	1.0	58.0 (2)	Sandstone, Fine-Grain, Clean.
3 4811-12	74 ✓	72	16.9 ✓	2.4	43.1 (2)	Sandstone, Fine-Grain, Clean.
4 4812-13	0.0	0.0	11.8	0.0	79.5 (2)	Sandstone, Fine-Grain, Numerous Thin Shale Laminations.
5 4813-14	0.9	0.0	16.2	1.2	80.3 (2)	Sandstone, Fine-Grain, Numerous Thin Shale Laminations.
6 4814-15	20 ✓	15	16.6 ✓	0.0	72.2 (2)	Sandstone, Fine-Grain, Numerous Thin Shale Laminations.
7 4817-18	0.0	0.0	12.0	0.0	76.5 (2)	Sandstone, Fine-Grain, Numerous Thin Shale Laminations, Clay Filled.
8 4820-21	24 ✓	15	20.6 ✓	1.0	66.0 (2)	Sandstone, Fine-Grain, Clean.
9 4821-22	112 ✓	23	20.4 ✓	1.0	58.0 (2)	Sandstone, Fine-Grain, Occasional Thin Shale Laminations.
10 4822-23	2.8	0.0	19.4	0.0	79.9 (2)	Sandstone, Fine-Grain, Numerous Thin Shale Laminations, Some Clay Filling.
11 4823-24	8.5	1.3	20.0	1.0	76.5 (2)	Sandstone, Fine-Grain, Carbonaceous trash.

319  
53 Md.

114.1  
19.0%

4824  
4530  
-294

NOTE: (1) REFER TO ATTACHED LETTER (2) OFF LOCATION ANALYSES - NO INTERPRETATION OF RESULTS  
(3) INCOMPLETE CORE RECOVERY - INTERPRETATION RESERVED

These analyses, figures, or interpretations are based on observations and materials supplied by the client or known, and for whose exclusive and confidential use this report is made. The interpretations or figures expressed represent the best judgment of Core Laboratories, Inc. (all errors and omissions excepted); by Core Laboratories, Inc. and its officers and employees, capable to responsibility and make no warranty or representation, as to the production, proper operation or profitability of a well, gas or other mineral well or sand or sandstone formation with which such report is used or relied upon.