

Chaco Energy Co.
Wellbore Schematic**Champlin 360 Amoco A #4**API: 05-017-06501
NW SE 29-12S-44W
2010' FSL & 1980' FEL
Cheyenne County, CO, Archer Field
38.977254, -102.359875**Well History - Significant Events****General Well Info:**Spud Date: 12/16/1984
Completion Date: 1/31/1985 (Osage)
Re-completion Date: NA
Status: P&A - 8/21/1995KB: 10' AGL
GL: 4359' ASL**Conductor:**

Unknown

Surface Hole: 12-1/2"**Surface Casing:**9-5/8" 32.3# J55 (?) @ 818'
Cmt w/ 700 sx**Prod Hole:** 8-3/4"

10 sx surface plug, 5 sx in 7" & 5 sx in 7" X 9-5/8" annulus

Perforate @ 2,890' (8/21/1995). Squeeze w/ 100 sx. Test to 400# f/ 10 min - good

Est. 7" TOC = 4,035'
Assume 20% excess & 1.14 ft^3/sk

CIBP @ 5590' w/ 2 sx

Osage - 5,678' - 88' & 5,656' - 62' (4 SPF)

Production Casing:7" 20# & 23# K55 (?) STC (?) @ 5734'
Cmt w/ 280 sxHole TD: 5734'
PBTD: ?
Last COTD: ?

Schematic not to scale

Date: 1/17/2024
Modified by: MTN