

- NOTES:
- EXISTING UTILITIES DISPLAYED ON THE GRADING PLAN ARE FOR REFERENCE PURPOSES ONLY. PRIOR TO CONSTRUCTION OR EARTHWORK, CONTRACTOR WILL BE RESPONSIBLE TO CALL FOR LOCATES: (800) 922-1987
 - THE 8' TALL BERM IS TO BE CONSTRUCTED UTILIZING ±19,000 C.Y. OF BASE MATERIAL AT APPROXIMATELY 5.0' FEET OF HEIGHT AND COVERED WITH ±6,802 C.Y. OF TOPSOIL TO REACH THE EFFECTIVE 8' TALL BERM HEIGHT.
 - RECLAIMED AREA WILL BE RE-SEEDING AND RE-VEGETATED DURING INTERIM RECLAMATION.

RAINBOW 24-9HZ INTERIM RECLAMATION SUMMARY

QUANTITIES AND DESIGN PARAMETERS

SHRINKAGE FACTOR = 1.00
SWELL FACTOR = 1.00
PROPOSED OIL & GAS LOCATION = 26.26 ACRES
AREA RECLAIMED DURING INTERIM RECLAMATION = 17.82 ACRES
TOTAL WELL PAD AREA AFTER INTERIM RECLAMATION = 4.83 ACRES
TOTAL FACILITY PAD AREA AFTER INTERIM RECLAMATION = 3.61 ACRES

WELL/FACILITY PAD QUANTITIES

TOTAL CUT = 47,847 C.Y.
TOTAL FILL = 47,847 C.Y.
TOTAL EXPORT = 0 C.Y.
TOPSOIL FROM WELL PAD = 16,216 C.Y.
TOPSOIL FROM FACILITY/TEMP EQUIPMENT PADS = 9,446 C.Y.
TOTAL TOPSOIL = 25,662 C.Y.
TOPSOIL USED FOR INTERIM REC = 12,055 C.Y.
TOPSOIL STORED FOR FINAL REC = 13,607 C.Y.
LAND USE: DRYLAND CROP

RAINBOW 24-9HZ

INTERIM RECLAMATION
RAINBOW 9-1HZ, RAINBOW 9-2HZ, RAINBOW 9-3HZ, RAINBOW 9-4HZ, RAINBOW 9-5HZ, RAINBOW 9-6HZ, RAINBOW 9-7HZ, RAINBOW 9-8HZ, RAINBOW 9-9HZ, RAINBOW 9-10HZ, RAINBOW 9-11HZ, RAINBOW 9-12HZ, RAINBOW 9-13HZ, RAINBOW 9-14HZ, RAINBOW 9-15HZ, RAINBOW 9-20HZ, RAINBOW 9-22HZ, RAINBOW 9-16HZ, RAINBOW 9-17HZ, RAINBOW 9-18HZ, RAINBOW 9-19HZ, RAINBOW 9-20HZ (TO BE P&A), RAINBOW 9-21HZ & RAINBOW 9-22HZ (TO BE P&A)
LOCATED IN SECTION 9, T5N, R67W, 6TH P.M.
GREELEY, COLORADO

Kerr-McGee Oil &
Gas Onshore LP
1099 18th Street
Denver, Colorado 80202




LOVELAND OFFICE
6706 North Franklin Avenue
Loveland, Colorado 80538
Phone 970-776-4331
SHERIDAN OFFICE
1095 Saberton Avenue
Sheridan, Wyoming 82801
Phone 307-674-0609

CONSULTING, LLC

LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- EXISTING CONTOURS (1' INTERVAL)
- PROPOSED CONTOURS (1' INTERVAL)
- EPL
- EXISTING PIPELINE
- EXISTING FLOWLINE
- EXISTING BURIED POWERLINE
- EXISTING GAS LIFT LINE
- EXISTING CHEM LINE
- EXISTING FENCE
- RECLAMATION AREA
- BERM



HORIZONTAL 0 75' 150' 1" = 150'

1' CONTOURS

SCALE: 1"=150' DATE: 2/6/24 SHEET NO: 1 OF 1
REVISED: SRS 2/8/24