

FORM

2

Rev
05/22

State of Colorado

Energy & Carbon Management Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203

Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

403645723

Date Received:

01/18/2024

APPLICATION FOR PERMIT TO

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate
Amend ☐
 TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: _____
Refile ☐
 ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐
Sidetrack ☐

Well Name: King 3-65

Well Number: 28-29 2BH

Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC

COGCC Operator Number: 10633

Address: 555 17TH STREET SUITE 3700

City: DENVER

State: CO

Zip: 80202

Contact Name: Jeff Annable

Phone: (303)312-8529

Fax: ()

Email: jannable@civiresources.com

FINANCIAL ASSURANCE FOR PLUGGING, ABANDONMENT, AND RECLAMATION

COGCC Financial Assurance

☒ The Operator has provided or will provide Financial Assurance to the COGCC for this Well.

Surety ID Number (if applicable): 20160104

Federal Financial Assurance

☐ In checking this box, the Operator certifies that it has provided or will provide at least this amount of Financial Assurance to the federal government for this Well. (Per Rule702.a.)

Amount of Federal Financial Assurance \$ _____

WELL LOCATION INFORMATION

Surface Location

QtrQtr: NESE Sec: 28 Twp: 3S Rng: 65W Meridian: 6

Footage at Surface: 1778 Feet FNL/FSL FSL 435 Feet FEL/FWL FEL

Latitude: 39.759379

Longitude: -104.660996

GPS Data:

GPS Quality Value: 2.1

Type of GPS Quality Value: PDOP

Date of Measurement: 06/28/2023

Ground Elevation: 5585

Field Name: DJ HORIZONTAL NIOBRARA

Field Number: 16950

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 28 Twp: 3S Rng: 65W

Footage at TPZ: 2200 FNL 330 FEL

Measured Depth of TPZ: 8185

True Vertical Depth of TPZ: 7690

FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 29 Twp: 3S Rng: 65W Footage at BPZ: 2200 FNL 330 FWL
Measured Depth of BPZ: 18104 True Vertical Depth of BPZ: 7690 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 29 Twp: 3S Rng: 65W Footage at BHL: 2200 FNL 330 FWL
FNL/FSL FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATION

County: ADAMS Municipality: Aurora

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of §
24-65.1-108 C.R.S.? No

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No

☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 12/19/2023

Comments: Case Number 2018-6001-01

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Mineral Owner beneath this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Surface Owner Protection Bond (if applicable): _____ Surety ID Number (if applicable): _____

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- ☒ Fee
☐ State
☐ Federal
☐ Indian
☐ N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

* If this Well is within a unit, describe a lease that will be developed by the Well.

* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

Township 3 South, Range 65 West
Section 28: All

Total Acres in Described Lease: 640

Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 4308 Feet
Building Unit: 4267 Feet
Public Road: 428 Feet
Above Ground Utility: 405 Feet
Railroad: 5280 Feet
Property Line: 435 Feet

INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-1457	1280	T3S R65W SEC 28: ALL, SEC 29: ALL

Federal or State Unit Name (if appl): _____

Unit Number: _____

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 330 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 600 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: _____ Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: _____ Feet

Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers. _____

SPACING & FORMATIONS COMMENTS

DRILLING PROGRAM

Proposed Total Measured Depth: 18104 Feet

TVD at Proposed Total Measured Depth 7690 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: _____ Feet ☒ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than

or equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted? _____

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	A53B	36.95	0	80	105	80	0
SURF	13+1/2	9+5/8	J-55	36	0	3251	1323	3251	0
1ST	8+1/2	5+1/2	P-110	20	0	18104	2852	18104	

☐ Conductor Casing is NOT planned

POTENTIAL FLOW AND CONFINING FORMATIONS

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Denver	24	24	760	760	0-500	Groundwater Atlas	USGS HA-646 (Robson & Romero, 1981)
Groundwater	Arapahoe	760	760	1413	1410	0-500	Groundwater Atlas	USGS HA-647 (Robson et al, 1981)
Groundwater	Laramie-Fox Hills	1413	1410	1977	1960	0-500	Groundwater Atlas	USGS HA-650 (Robson et al, 1981)
Confining Layer	Pierre Formation	1977	1960	2480	2450			
Groundwater	Upper Pierre	2480	2450	3158	3110	501-1000	Electric Log Calculation	Flader Industries Inc B-1 (05-005-06536-0000)
Confining Layer	Base of Upper Pierre	3158	3110	4252	4175			
Hydrocarbon	Parkman Sandstone	4252	4175	4380	4300			Not productive in this area
Confining Layer	Pierre Formation	4380	4300	5356	5250			
Hydrocarbon	Sussex Sandstone	5356	5250	5556	5445			Not productive in this area
Confining Layer	Pierre Formation	5556	5445	6151	6025			
Hydrocarbon	Shannon Sandstone	6151	6025	6578	6440			Not productive in this area
Confining Layer	Pierre Formation	6578	6440	7917	7630			
Subsurface Hazard	Sharon Spring	7917	7630	8185	7690			Sloughing shales
Hydrocarbon	Niobrara	8185	7690	18104	7690			

OPERATOR COMMENTS AND SUBMITTAL

Comments

The distance to the completed portion of the nearest well in the same unit on the "Spacing & Formation" tab is measured to the proposed King 3-65 28-29 2AH. This distance was measured in 2-dimensional space.

There are no existing or proposed wellbores belonging to another operator, including plugged wells within 1500' of this proposed wellbore.

This application is in a Comprehensive Area Plan Yes

CAP #: 210700116

Oil and Gas Development Plan Name King 3-65 28-29 OGD

OGDP ID#: 485274

Location ID: 449176

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Jeff Annable

Title: Manager, Regulatory

Date: 1/18/2024

Email: jannable@civiresources.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: 2/12/2024

Expiration Date: 12/19/2026

API NUMBER

05 001 10566 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
Planning	Pursuant to Rule 702.b.(2), the approval of this Application for Permit to Drill constitutes a "change in circumstance" to the approved Financial Assurance Plan. The Operator must file a revised Form 3, Financial Assurance Plan, within 10 days of this approval.
Interim Reclamation	Operator shall comply with Notice to Operators: Interim Reclamation Procedures for Delayed Operations (dated January 5, 2017).
Construction	If conductors are preset, operator shall comply with Notice to Operators: Procedures for Preset Conductors (dated September 1, 2016).
Drilling/Completion Operations	Operator will log three (3) additional wells during the second rig occupation with open-hole resistivity log with gamma-ray log from the kick-off point into the surface casing for the stratigraphically deepest wells for a total of four wells logged.
Drilling/Completion Operations	Per COGCC Order 1-232, Bradenhead tests shall be performed according to the following schedule and Form 17 submitted within 10 days of each test: 1) Within 60 days of rig release, prior to stimulation. If any pressure greater than 200 psi is observed or if there is continuous flow, Operator must contact COGCC engineering for approval prior to stimulation. 2) If a delayed completion, a second test is required between 6-9 months after rig release and must be conducted prior to stimulation. If any pressure greater than 200 psi is observed or if there is continuous flow, Operator must contact COGCC engineering for approval prior to stimulation. 3) A post-production test within 60 days after first sales, as reported on the Form 10, Certificate of Clearance.
Drilling/Completion Operations	1) Submit Form 42 electronically to COGCC 2 business days prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 2 business day spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Comply with Rule 408.j. and provide cement coverage from TD to a minimum of 500' above Niobrara. Verify coverage with a cement bond log.
6 COAs	

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	One of the first wells drilled on the pad during the first rig occupation will be logged with open-hole resistivity log with gamma-ray log from the kick-off point into the surface casing for one of the stratigraphically deepest wells on the pad. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs will state "Alternative Logging Program - No open-hole logs were run" and will clearly identify the type of log and the well (by API#) in which open-hole logs were run.
2	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.

Total: 2 comment(s)

Attachment List

<u>Att Doc Num</u>	<u>Name</u>
403645723	FORM 2 SUBMITTED
403645746	DEVIATED DRILLING PLAN
403645747	DIRECTIONAL DATA
403645748	WELL LOCATION PLAT
403651239	OffsetWellEvaluations Data
403683658	OFFSET WELL EVALUATION

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed.	02/08/2024
Permit	Emailed operator requesting: addition of OH Logging, Conductor & Interim Reclamation COAs.	02/02/2024
OGLA	The Commission approved OGDG #485274 on December 20, 2023 for the Oil and Gas Location related to this Form 2. OGLA task passed.	01/19/2024

Total: 3 comment(s)