

file

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

(Indicate nature of data by checking below)



Notice of intention to drill (attach plat) _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report x

Locate Well Correctly

Notice to do work ☐
 Report of work done ☒

Land: Fee and Patented ☐
 State ☐

Lease No. _____

Colorado
 State

Morgan
 County

Burr
 Field

22 (Well No.) G. E. Huey (Lease) SE SW (1/4 Sec.) 29 (Sec.) 2N (Twp.) 56W (Range) 6 (Meridian)

The Well is located 915 Ft. (N) of Section Line and 1744 Ft. (E) of
 Section Line. (S) (W)

The elevation above sea level is 4426.0' Ft. G. L.

Details of Plan of Work: (State names of and expected depths to objective sands.
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
 points, and all other important proposed work.)

Drilled well to 5295' T D.
 Ran combination Induction Electrical log.
 Ran Drill Stem Test W/ straddle packer from 5192' to 5200'.
 Set 99' of 10 3/4" -32.75# casing w/125 sacks cement. 2% Cal. Chloride.
 Set 5295' 5 1/2" - 14# Casing w/150 sacks of neat cement.
 Perforated from 5190' to 5196' w/ 6 shots per ft.
 Completed well as producer in Dakota "D" sand.

AJJ	
DVR	
WRS	✓
HMM	
JAM	✓
FJP	✓
UD	
FILE	

RECEIVED
FEB 13 1958

OIL & GAS
CONSERVATION COMMISSION

Approved: 2-13-58

Lee R. Stockard
 Director

Date Jan. 27, 1958

Company H. L. Hunt

Address 700 Merc. Bank Bldg.
Dallas 1, Texas

By Lee R. Stockard

Title Field Supt.

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.