


OGCC



00599648

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompleation	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Mary Snyder WELL NO. 1
 FIELD Xenia, West WILDCAT _____ COUNTY Washington
 LOCATION NE SE Section 10 Township 2N Range 54W Meridian 6th
 (Quarter Quarter)
1982 feet from S Section Line and 666 feet from E Section Line
 N or S E or W

(DETAILS OF WORK)

Set 4 jts., 126½' of 7" surface casing 134' from D.B. Cemented with 125 sacks of regular cement, 2% calcium chloride. Cement circulated to surface. Well was drilled to T.D., 4827' and found to be non-productive.

It is proposed to fill hole with mud, 4827-134'; 15 sacks of cement, 134-57'; mud, 57-50'; 10 sacks of cement, 50' to surface. Will erect permanent marker.

✓ This is to confirm plugging procedure agreed upon in telephone conversation between Mr. Irvyn Colwell and Mr. A. J. Jersin May 31, 1960.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	✓
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Date June 3 1960
 Director [Signature]

Company Kingwood Oil Company Date 6-1-60
 First National Building
 Address Oklahoma City, Oklahoma Phone No. CE 6-3771
 By [Signature] Title Chief Clerk
 (Signature)