

FORM  
2

Rev  
05/22

# State of Colorado

## Energy & Carbon Management Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

403697042

**(SUBMITTED)**

Date Received:

02/27/2024

### APPLICATION FOR PERMIT TO

Drill     Deepen     Re-enter     Recomplete and Operate

Amend

TYPE OF WELL OIL  GAS  COALBED  OTHER: \_\_\_\_\_

Refile

ZONE TYPE SINGLE ZONE  MULTIPLE ZONES  COMMINGLE ZONES

Sidetrack

Well Name: Opal Well Number: 5

Name of Operator: BAYSWATER EXPLORATION & PRODUCTION LLC COGCC Operator Number: 10261

Address: 730 17TH ST STE 500

City: DENVER State: CO Zip: 80202

Contact Name: Lauren Walsh Phone: (720)881-4502 Fax: ( )

Email: lwalsh@bayswater.us

### FINANCIAL ASSURANCE FOR PLUGGING, ABANDONMENT, AND RECLAMATION

#### COGCC Financial Assurance

The Operator has provided or will provide Financial Assurance to the COGCC for this Well.

Surety ID Number (if applicable): 20080034

#### Federal Financial Assurance

In checking this box, the Operator certifies that it has provided or will provide at least this amount of Financial Assurance to the federal government for this Well. (Per Rule702.a.)

Amount of Federal Financial Assurance \$ \_\_\_\_\_

### WELL LOCATION INFORMATION

#### Surface Location

QtrQtr: NESE Sec: 6 Twp: 7N Rng: 66W Meridian: 6

Footage at Surface: 2455 Feet FSL 584 Feet FEL

Latitude: 40.603128 Longitude: -104.813097

GPS Data: GPS Quality Value: 1.9 Type of GPS Quality Value: PDOP Date of Measurement: 10/30/2022

Ground Elevation: 5129

Field Name: DJ HORIZONTAL NBRR-FH-CODL-CL Field Number: 16952

Well Plan: is  Directional  Horizontal (highly deviated)  Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

#### Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 6 Twp: 7N Rng: 66W Footage at TPZ: 2018 FNL 160 FEL

Measured Depth of TPZ: 7847 True Vertical Depth of TPZ: 7352 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 1 Twp: 7N Rng: 67W Footage at BPZ: 2010 FNL 160 FWL
Measured Depth of BPZ: 18598 True Vertical Depth of BPZ: 6992 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 1 Twp: 7N Rng: 67W Footage at BHL: 2010 FNL 160 FWL
FNL/FSL FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATION

County: WELD Municipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? Yes

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I) (A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? [X] Yes [ ] No

[X] If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 05/05/2023

Comments: 1041WOGLA22-0018 submitted 12/9/2022, approved 5/5/2023.

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: [X] Fee [ ] State [ ] Federal [ ] Indian

Mineral Owner beneath this Well's Oil and Gas Location: [X] Fee [ ] State [ ] Federal [ ] Indian

Surface Owner Protection Bond (if applicable): Surety ID Number (if applicable):

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- [X] Fee
[ ] State
[ ] Federal
[ ] Indian
[ ] N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

\* If this Well is within a unit, describe a lease that will be developed by the Well.
\* If this Well is not subject to a unit, describe the lease that will be produced by the Well.
(Attach a Lease Map or Lease Description or Lease if necessary.)

Lot 1-7, S2NE, SENW, NESW, NESE; Sec 6, T7N, R66W

Total Acres in Described Lease: 545 Described Mineral Lease is: [X] Fee [ ] State [ ] Federal [ ] Indian

Federal or State Lease #

**SAFETY SETBACK INFORMATION**

Distance from Well to nearest:

Building: 2518 Feet  
 Building Unit: 2643 Feet  
 Public Road: 2445 Feet  
 Above Ground Utility: 618 Feet  
 Railroad: 5280 Feet  
 Property Line: 190 Feet

**INSTRUCTIONS:**

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

**OBJECTIVE FORMATIONS**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-3551	1280	7N-67W:1;7N-66W:6

Federal or State Unit Name (if appl): \_\_\_\_\_

Unit Number: \_\_\_\_\_

**SUBSURFACE MINERAL SETBACKS**

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 160 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 415 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: \_\_\_\_\_ Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: \_\_\_\_\_ Feet

**Exception Location**

If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers. \_\_\_\_\_

**SPACING & FORMATIONS COMMENTS**

## DRILLING PROGRAM

Proposed Total Measured Depth: 18598 Feet

TVD at Proposed Total Measured Depth 6992 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 13 Feet  No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No If yes, attach an H<sub>2</sub>S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type:  Annular Preventor  Double Ram  Rotating Head  None

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_





Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

<b>API NUMBER</b>
05

**Conditions Of Approval**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
0 COA	

**Best Management Practices**

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	Alternative Logging Program - One of the first wells drilled on the pad will be logged with Open Hole Resistivity Log and Gamma Ray Log from the kick-off point to into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open hole logs shall clearly state "Alternative Logging Program - No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open hole logs were run.
2	Drilling/Completion Operations	Blowout Prevention Equipment ("BOPE"): A double ram and annular preventer will be used during drilling. Stabbing valves shall be installed in the event of reverse circulation and shall be prior tested with low- and high-pressure fluid.
3	Drilling/Completion Operations	Bradenhead Monitoring: Operator acknowledges and will comply with COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
4	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.

Total: 4 comment(s)

**Attachment List**

<u>Att Doc Num</u>	<u>Name</u>
403697180	OffsetWellEvaluations Data
403697192	WELL LOCATION PLAT
403697194	DEVIATED DRILLING PLAN

Total Attach: 4 Files

**General Comments**

**User Group**

**Comment**

**Comment Date**

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)

