


OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

99999999

## PLUGGING RECORD



## INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Miami Petroleum Company, Inc. 56905 Field Buffalo Slough Wildcat  
Lease Name E. C. Wenig "A" Well No. 4 County Washington  
Location SE $\frac{1}{4}$  SW $\frac{1}{4}$  Section 14 Township 2N Range 54W Meridian Sixth  
993 (Quarter Quarter) feet from S Section line and 1992 feet from W Section Line  
N or S E or W

TOTAL DEPTH 4815'DATE OF PLUGGING 12/1/61

## DETAILS OF WORK

5 $\frac{1}{2}$ " OD casing was shot off and 3778' pulled = 1033' left in hole  
123' of 8 $\frac{5}{8}$ " J=55 24# surface casing was left in hole. Hole was filled with heavy mud, gravel, and cement plugs as follows:

Plug No. 1 = Heavy mud, cement (5 sacks) and gravel from 4815' to 4770'  
Plug No. 2 = 143' to 103' = 10 sack cement plug  
Plug No. 3 = 30' to 0 = 5 sack cement plug

Dry Hole Plug was placed in top, and marker erected.



00566942

121-06905

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date DEC 29 1961

Director

Company Miami Petroleum Co. Inc. Date 12/27/61

P. O. Drawer 2040

Address Abilene, TexasPhone No. OR 4-6253

By

(Signature)

Title Vice President