



00048430

H&R Well Services, Inc.
17509 Rd 14
Ft. Morgan, Colorado 80701
303-432-5285 or 654-1600 (metro)

December 29, 1990

Mr. Larry Childers
PETEX, Inc.
11 S. Gleastone, Ste 104
Springfield, Missouri 65804

RECEIVED

APR 23 1991

Lease: Huey 1 -32
Morgan County, Colo
NW SW SW Sec 32 - 2N - 56W

COLO.OIL & GAS CONS.COMM'

Mr. Childres,

We performed the following work on the above lease. This letter should be attached to a Form 4 as a cement verification, and forwarded to the Colorado Oil and Gas Commission.

Set a CIBP and 3 sacks above perfs at 5,100'.
Loaded the hole.
Cut and pulled casing from 4,312'.
Laid down casing.
Ran in the hole with tubing to the base of surface pipe.
Set 30 sacks of cement 1/2 in 1/2 out at base of 8 5/8 at 96'.
Set 5 sacks at surface.
Cut wellhead off 4' down.
Welded a plate.
Backfilled the hole.

Sincerely,

Dave Rebol
H&R Well Services, Inc.