

BEST IMAGE  
AVAILABLE

1x65 = 45.5

H&R Well Services, Inc.  
17509 Rd 14  
Ft. Morgan, Colorado 80701  
303-432-5285 or 654-1600 (metro)



00048429

December 29, 1990

Mr. Larry Childers  
PETEX, Inc.  
11 S. Gleestone, Ste 104  
Springfield, Missouri 65804

Lease: Huey 1 -32  
Morgan County, Colo  
NW 8W SW Sec 32 - 2N - 56W

Mr. Childers,

We performed the following work on the above lease. This letter should be attached to a Form 4 as a cement verification, and forwarded to the Colorado Oil and Gas Commission.

Set a CIBP and 3 sacks above perfs at 5,100'.  
Loaded the hole.  
Cut and pulled casing from 4,312'.  
Laid down casing.  
Ran in the hole with tubing to the base of surface pipe.  
Set 30 sacks of cement 1/2 in 1/2 out at base of 8 5/8 at 96'.  
Set 5 sacks at surface.  
Cut wellhead off 4' down.  
Welded a plate.  
Backfilled the hole.

Sincerely,

Dave Rebol  
H&R Well Services, Inc.

FRANK HUTTO

867-6298 ELDER  
6298 NATI  
WAYNE TANKS