



OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO

RECEIVED

JAN - 3 1967

PLUGGING RECORD

COLO. OIL & GAS CONS. COMM.

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator H. L. HuntField Un-named "J" Sand WildcatLease Name Arthur Peterson et alWell No. 3 County MorganLocation SE/4 NW/4
(Quarter Quarter)Section 35Township 2NRange 56WMeridian 6

1938'

feet from S-N
N or S

Section line and

2007'

feet from E
E or W

Section Line

TOTAL DEPTH 5320'DATE OF PLUGGING Dec. 30, 1966

DETAILS OF WORK

Filled 5 1/2" Casing with sand from bottom up to 5100'. Set 5 sack cement plug rom 5100' up to 5064'. Shot casing off at 4061'. Pulled and laid down casing. Filled hole with heavy viscous mud. Set 10 sack cement plug in bottom of surface casing and 5 sack cement plug in top of surface pipe. Welded steel plate across top of surface pipe. Well Plug and Abandoned.

EX
GAS
Prod.

DVR	
WBS	
HFM	
JAM	
FJP	✓
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JAN 9 1967

Director

Company H. L. HuntDate 12/31/66

1401 Elm

Address Dallas, Texas 75202Phone No. Ri 1-3561

By

C. E. Zancy
(Signature)Title Supt.