



RECEIVED

WELL NAME: Talbert #2
AREA: SW Stockholm
LOCATION: Sec. 18-T16S-R41W
COUNTY: Cheyenne
STATE: Colorado
FOOTAGE: 1650' FNL, 1650' FEL
AFE\$: 183,000

PTD: 5300'
ELEVATIONS: (Est) 3925' KB, 3915' EL
CONTRACTOR: Murfin
AFE NUMBER: 861994
LSE NUMBER: 78034
TXO WI: 37.5%
FIELD OFFICE: Lamar

JUN 23 1986
COLD OIL & GAS COMMISSION

- 05/23/86 1940' (1572'), drlg. Sh. Native. Misrun @ 868'. 7/8" @ 1110'.
1-3/4" @ 1634'. 1-1/4" @ 1900'. Tested BOP to 1000# for 15 min, all
held. Drld plug @ 2 PM 5/22/86. DW: 11,772. CW: 20,989. DD 2.
- 05/24/86 2870' (930'), drlg. Sh & lm. 9.5, 28. 1-1/4" @ 2140'. 1-1/2" @
2640'. Anhydride top @ 2732'. Base @ 2769'. DW: 7921. CW:
28,280. DD 3.
- 05/25/86 3475' (605'), drlg. Sh & lm. 9.3, 28. 1" @ 3124'. DW: 5587. CW:
33,867. DD 4.
- 05/26/86 3940' (465'), drlg. Sh. Native. 1" @ 3748'. Trip for cracked
collar. DW: 4441. CW: 38,308. DD 5.
- 05/27/86 4585' (645'), drlg. Lm & sh. 1" @ 4253'. Lost circ @ 4014'. Lost
approx 120 bbls, pumped 40 bbl pill. Regained circ. DW: 6526. CW:
44,834. DD 6.
- 05/28/86 5005' (420'), drlg. Lm/sh. 8.8, 52, 8. Displace hole w/ 960 bbls
premixed mud. 3/4" @ 4700'. DW: 4397. CW: 49,231. DD 7.
- 05/29/86 5300' (295'), circ for logs. Miss. 9.2, 55, 8.4. TD 7-7/8" hole @
3:15 AM on 5-29-86. Circ for 1-1/2 hrs, made 15 std ST, no fill.
Circ for 2 hrs. DW: 3,187. CW: 52,418. DD 8.
- 05/30/86 5300' (0'), WOO. TOOH. RU Gearhart. Run logs. WO tester. Make up
tools. TIH w/ DST #1. Attempt to place packers @ 5146'-5182'.
Packers wouldn't hold. TOOH. 1" @ 5300'. DW: 6,818. CW: 59,236.
DD9.
- 05/31/86 5300' (0'), WO Loggers. Lm/sh. WO Tester. PU & RIH w/ DST #2. Set
packers & run DST #2. Rls pkrs & TOOH. BD DST tools. 9.3, 64, 8.2.
DST #2 from 5025'-5185' (Morrow). IFP, TO w/ weak blow, increased to
4" in bucket in 3 min. Stabilized for remainder of flow period. FFP,
TO w/ weak blow. Off btm of bucket in 10 min. Stabilized for
remainder of period. Rec 240' O&GCM. IHHP 2530#, 30" IFP 114-157#,
60" ISIP 939#, 60" FFP 157-214#, 120" FSIP 939#, FHHP 2331#, BHT
138°F. BHSC @ 360#, .8 cu ft gas, 2200 cc OCM. Grind out 20% oil.
DW: 6,360. CW: 65,596. DD 10.
- 06/01/86 5300' (0'), MORT. RU Schlumberger. Run Dipmeter Survey Log. RIH &
LD DC. TIH & set 35 sx cmt plug @ 5150'. TOOH. LD DP. Set 25 sx
cmt plug @ 368'. TOOH. Set 40 sx plug @ surface. Set 5 sx in MH.
Well P & A'd. RR @ 9:30 PM 5-31-86. DW: 7,399. CW: 72,995.
FINAL REPORT!!!!

WELL NAME: Talbert #2
AREA: SW Stockholm
LOCATION: Sec. 18-T16S-R41W
COUNTY: Cheyenne
STATE: Colorado
FOOTAGE: 1650' FNL, 1650' FEL
AFE\$: 183,000

PTD: 5300'
ELEVATIONS: (Est) 3925'KB, 3915'GL
CONTRACTOR: Murfin
AFE NUMBER: 861994
LSE NUMBER: 78034
TXO WI: 37.5%
FIELD OFFICE: Lamar

Remuda Corp.
P.O. Box 7127
Billings, Montana
59103-7127
Attn: Judy Brewer
Phone No. (406) 259-4296
WI: 12.5%

Daily Call
Weekly Mail

RECEIVED

JUN 23 1986

GOLD OIL & GAS CORP. COMM

Southern Century, Inc.
900-401 9th Ave. SW
Calgary, Alberta
Canada T2P 3C5
Attn: Gordon McLoud
Phone No. (403) 262-2883
WI: 12.5%

Weekly Mail

Char Holdings, Ltd.
Mainland Pet. Co.
1960 Sunlife
Plaza St.
144 4th Ave. SW
Calgary, Alberta
Canada T2P 3N4
Phone No. (403) 262-5542
WI: 10%

Weekly Mail

DCX Resources, Ltd.
1776 Lincoln Street
Suite 601
Denver, Colorado 8020
Attn: Harry Veal
Phone No: 861-4295
JAM Struharik
WI: 6.25%

Daily Call
Weekly Mail

Security Resources Corp.
2900 Security Life Bldg.
1616 Glenarm Place
Denver, Colorado 80203
Attn: Holms McLish
Phone No: 534-3052
Evelyn Schippers
WI: 6.25%

Daily Call
Weekly Mail

Larne Holdings, Inc.
715 Madison Ave. SW
Calgary, Alberta
Canada
Attn: William LeSourd
Phone No: (403) 263-5662
WI: 2.5%

Daily Call
Weekly Mail

APCOT-Finadel Joint Venture
P.O. Box 2159
Dallas, Texas 75521
Attn: Houston Welch
Phone No: (214) 750-2400
WI: 25%

Weekly Mail

05/22/86 368' (368'), WOC. 9.4, 35. 1/2° @ 150'. 3/4° @ 240'. 1/4° @ 368'.
MI & RU Murfin Rig #23. Spud 12-1/4" hole @ 6 PM 5/21/86. TD
12-1/4" hole @ 11:30 PM 5/21/86. Ran 9 jts 8-5/8", 24#, K-55, ST&C
csg (368'). Cmt'd w/ 100 sxs of Halco lite w/ 3% CaCl₂. Tail w/ 75
sxs of Cl "C" w/ 3% CaCl₂. PD @ 5 AM. DW: 9217. CW: 9217. DD 1.