



P&A Wellbore For State

Well Name: WILMOTH C14-25

Original Hole [Land]		Well Header									
MD (ftK B)	Vertical schematic (actual)	Surface UWI 0512329730		Business Unit Rockies		Gov Auth Dist		Prod Tree Loc Land			
		Orig. KB to Gnd (ft) 15.00		Original Spud Date 11/1/2009		Abandon Date		Well Sub-Status PR		High... N	
Comment KMG ADDED AS PARTNER AFTER WELL WAS DRILLED - PARTNER REPORTS & LOGS WILL BE SENT 2/8/10 - kpp											
Surface Location (Congressional)											
Qtr 3 NE		Qtr 4 SW		Section 14	Twnshp 4	Twnsh... N	Range 64	Rng E/... W	Latitude (°) 40.30928428	Longitude (°) -104.522394949	
Wellbore Sections											
Section Des		Hole Size (in)		Top Depth (ftKB)		Btm Depth (ftKB)					
SURFACE		12 1/4		15.0		586.0					
PRODUCTION		7 7/8		586.0		6,944.0					
Casing Strings											
Csg Des		Run Date		OD (in)	Wt/Len (lb/ft)	Grade	Top Depth (MD) (ftKB)	Set Depth (MD) (ftKB)			
Surface		11/2/2009		8 5/8	24.00	J-55	15	573.4			
Production Casing		11/5/2009		4 1/2	11.60	M-80	15	6939.1			
Cement											
Des		Start Date		Top (ftKB)		Btm (ftKB)					
Surface Casing Cement		11/2/2009		15.0		573.4					
Production Casing Cement		11/5/2009		413.0		6,939.1					
Zone Statuses											
Zone Name		Status Date	Status	Fluid Type	Job			Prod Method			
NIOBRARA		12/12/2009	PR		DRILLING/COMPLETION - ORIGINAL, 10/31/200...						
CODELL		12/12/2009	PR		DRILLING/COMPLETION - ORIGINAL, 10/31/200...						
Perforation Data											
Linked Zone		Explosive Type	Entered Shot Total	Top (ftKB)		Btm (ftKB)		Date			
NIOBRARA, Original Hole		A	24	6,504.0		6,516.0		12/10/2009			
NIOBRARA, Original Hole		C	24	6,630.0		6,642.0		12/10/2009			
CODELL, Original Hole			48	6,746.0		6,758.0		11/23/2009			
Stim/Frac Stage											
Zone		Start Date		Top (ftKB)		Btm (ftKB)					
NIOBRARA, Original Hole		12/10/2009		6,504.0		6,516.0					
NIOBRARA, Original Hole		12/10/2009		6,630.0		6,642.0					
CODELL, Original Hole		12/10/2009		6,746.0		6,758.0					
Other In Hole											
Run Date		Des		Make		OD (in)	Top (ftKB)	Btm (ftKB)			
3/5/2024		Cast Iron Bridge Plug w/ 2 SX Cement				3.99	6,428.0	6,455.0			
Logs											
Date		Type				Depth Top (MD) (ftKB)		Btm (ftKB)			
11/4/2009		Caliper/Comp. Density/Neutron/GR/SP/ML				2,550		6,931.0			
11/4/2009		DIL/GR/SP/Caliper				573		6,951.0			
11/18/2009		CBL/CCL/GR				0		6,862.0			
Wellbore Plug Back Total Depths											
Date		Type		Com				PBTD (ftKB)			
11/5/2009		FLOAT COLLAR		FLOAT COLLAR				6,894			