



Colorado State Wells DIVISION **SCANNED** AS OF 7 A.M. October 6 1910

SCANNED

LEASE	WELL NO.	COMMENCED DRILLING	SIZE AND DEPTH LAST STRING CASING SET	FORMATION AND REMARKS	DEPTH YESTERDAY	DEPTH TODAY
Kiowa County McClave 7-15 Location: 330' FSL, 330' FEL, Sec. 11- 20S-49W. Elev: 4043' ground, RB 4054'.	1	8-15-52	10 3/4" 209'	Oct. 6: TD 5914'. Cemented 5 1/2' casing at 4858'. Drilling on float collars. Oct. 7: TD 5914'. Drilled & cleaned out to 4911', found no cement to that depth. Conditioned hole. DST w/hook wall packer at 4771' has now been open 4 hrs. Gas to surface in 35 mins., conditioning slight blow. Oct. 8: TD 5914'. DST gas sec. 4850-4900, hook wall packer set at 4777' in 5 1/2" csg. Open 11 hrs., shut in 20 min., had gas varying from 80 to 100 Mcf. maximum FP 300, SIP 1025 lbs. Well unloaded a bbl. or 2 of drilling fluid & we recovered 500' of drilling fluid in the tbg. Now circulating to clean up. Will run tbg. and swab. Oct. 9: TD 5914'. Ran 2" tbg. to 4880'. Swabbing drilling fluid. Oct. 10: TD 5914'. Swabbed to clean up drilling fluid - gas in- creased to approx. 150 Mcf. Preparing to acidize.	TD 5914'	TD 5914'
Kiowa County White Location: 330' FSL, 330' FEL, Sec. 20- 19S-45W. Elev: 3922' RB, 3913' ground.	1	10-4-52	10 3/4" 252'	Oct. 6: Spudded 12 a.m. 10/4. Drilled to 260' in shale. Cemented 10 3/4" csg. at 252'. Preparing to drill plug. Oct. 7: Drilling shale 922'. Sam- ple top Dakota 600'. Oct. 8: Drilling shale 1607'. Sample top Morrison 1078'. Oct. 9: Drilling Red Beds and anhydrite 2160'. Oct. 10: Drilling Red Beds and anhydrite 2460'.	0 260' 922' 1607' 2160' 2460'	260' 922' 1607' 2160' 2460'