

FORM

2

Rev
05/22

State of Colorado

Energy & Carbon Management Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

403671606

(SUBMITTED)

Date Received:

03/20/2024

APPLICATION FOR PERMIT TO

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and OperateAmend ☐TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: _____Refile ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: RADEMACHER SOUTH

Well Number: 30-13HZ

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

COGCC Operator Number: 47120

Address: P O BOX 173779

City: DENVER

State: CO

Zip: 80217-3779

Contact Name: Loryn Spady

Phone: (720)9293504

Fax: ()

Email: Loryn_Spady@oxy.com

FINANCIAL ASSURANCE FOR PLUGGING, ABANDONMENT, AND RECLAMATION

COGCC Financial Assurance

☒ The Operator has provided or will provide Financial Assurance to the COGCC for this Well.

Surety ID Number (if applicable): 20230087

Federal Financial Assurance

☐ In checking this box, the Operator certifies that it has provided or will provide at least this amount of Financial Assurance to the federal government for this Well. (Per Rule702.a.)

Amount of Federal Financial Assurance \$ _____

WELL LOCATION INFORMATION

Surface Location

QtrQtr: SESW Sec: 30 Twp: 3N Rng: 67W Meridian: 6

FNL/FSL

FEL/FWL

Footage at Surface: 508 Feet FSL 2054 Feet FWL

Latitude: 40.191310

Longitude: -104.934415

GPS Data:

GPS Quality Value: 1.4

Type of GPS Quality Value: PDOP

Date of Measurement: 04/11/2023

Ground Elevation: 4821

Field Name: WATTENBERG

Field Number: 90750

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 31 Twp: 3N Rng: 67W

Footage at TPZ: 1171 FNL 1050 FEL

Measured Depth of TPZ: 8062

True Vertical Depth of TPZ: 7246

FNL/FSL

FEL/FWL

Base of Productive Zone (BPZ)Sec: 6 Twp: 2N Rng: 67WFootage at BPZ: 225 FSL 1051 FELMeasured Depth of BPZ: 17379True Vertical Depth of BPZ: 7317 FNL/FSL FEL/FWL**Bottom Hole Location (BHL)**Sec: 6 Twp: 2N Rng: 67WFootage at BHL: 225 FSL 1051 FEL

FNL/FSL

FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATIONCounty: WELDMunicipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of §

24-65.1-108 C.R.S.? Yes

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I) (A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 11/18/2023Comments: WOGLA#: 1041WOGLA23-0013**SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION**Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ IndianMineral Owner beneath this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Surface Owner Protection Bond (if applicable):

Surety ID Number (if applicable):

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

☒ Fee☐ State☐ Federal☐ Indian☐ N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

* If this Well is within a unit, describe a lease that will be developed by the Well.

* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

Township 3 North, Range 67 West, 6th P.M.
Section 31: NW
Weld County, Colorado

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 1361 Feet
Building Unit: 1450 Feet
Public Road: 2042 Feet
Above Ground Utility: 1979 Feet
Railroad: 5280 Feet
Property Line: 477 Feet

INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-3582	1760	3N-67W-31: ALL; 2N-67W-6: ALL; 7: W2; 18: NW

Federal or State Unit Name (if appl): _____ Unit Number: _____

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 225 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 416 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: _____ Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: _____ Feet

Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers. _____

SPACING & FORMATIONS COMMENTS

DRILLING PROGRAM

Proposed Total Measured Depth: 17379 Feet

TVD at Proposed Total Measured Depth 7317 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 292 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than

or equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	ASTM A53 B	36.94	0	80	64	80	0
SURF	13+1/2	9+5/8	L80	36	0	1500	590	1500	0
1ST	7+7/8	5+1/2	HCP110	17	0	17369	1947	17369	1000

☐ Conductor Casing is NOT planned

POTENTIAL FLOW AND CONFINING FORMATIONS

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Fox Hills and Shallower	17	17	142	142	501-1000	USGS	Depth data from DWR
Confining Layer	Pierre Shale	143	143	381	381			
Groundwater	Upper Pierre Aquifer	382	382	1225	1220	501-1000	Electric Log Calculation	Controlled by samples
Confining Layer	Pierre Shale	1226	1221	4259	4067			
Hydrocarbon	Sussex	4260	4068	4463	4257			Productive
Confining Layer	Pierre Shale	4464	4258	4830	4599			
Hydrocarbon	Shannon	4831	4600	4882	4648			Non-productive
Confining Layer	Pierre Shale	4883	4649	7437	7000			
Hydrocarbon	Niobrara	7439	7001	7438	7243			*Niobrara base is 1' shallower than corresponding Codell top
Hydrocarbon	Codell	8013	7244	0	0			

OPERATOR COMMENTS AND SUBMITTAL

Comments

PLEASE ENSURE ALL CORRESPONDENCE ASSOCIATED WITH THIS PERMIT GOES TO ANALYST AND DJREGULATORY EMAIL ADDRESSES, AS LISTED ON THIS PERMIT.

Offset well buffer description for the subject well has been included on this permit for review as an attachment labeled "Other."

Base of Productive Zone is the same as Bottom Hole Location.

The nearest offset wellbore permitted or completed in the same formation is RADEMACHER SOUTH 30-14HZ, DOC ID: 403671620.

This application is in a Comprehensive Area Plan No CAP #: _____
Oil and Gas Development Plan Name SPROUT OGDP ID#: 485787
Location ID: 486288

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Loryn Spady
Title: Regulatory Analyst Date: 3/20/2024 Email: DJREGULATORY@OXY.COM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____
Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

0 COA

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	Kerr-McGee acknowledges and will comply with the ECMC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
2	Drilling/Completion Operations	Anti-Collision: Kerr-McGee will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within one hundred fifty (150) feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators within one hundred fifty (150) feet prior to drilling.
3	Drilling/Completion Operations	Open Hole Logging Exception: One of the first wells drilled on the pad will be logged with cased-hole neutron log with gamma-ray log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall state "Open Hole Logging Exception - No open-hole logs were run" and shall clearly identify the type of log and the well (by API#) in which open-hole logs were run.

Total: 3 comment(s)

Attachment List

<u>Att Doc Num</u>	<u>Name</u>
403679631	OTHER
403679632	WELL LOCATION PLAT
403679633	DEVIATED DRILLING PLAN
403679639	DIRECTIONAL DATA
403688444	OFFSET WELL EVALUATION
403688447	OPEN HOLE LOGGING EXCEPTION

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)