

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

PLUGGING RECORD

NOV 13 1957

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Walter S. Pendleton, Jr. Field Stony Point Wildcat
 Lease Name Windolph Well No. 1 County Washington
 Location SW - SE Section 20 Township 2N Range 54 Meridian 6th
 (Quarter Quarter)
~~660~~ feet from S Section line and ~~1320~~ feet from E Section Line
330 N or S 2310 E or W

TOTAL DEPTH 4876 DATE OF PLUGGING October 22, 1957

DETAILS OF WORK

We found total depth inside of casing @ 4876, filled with sand to 4850 (bottom of casing perforations), placed 5 sacks of cement from 4850 to 4810 foot, mudded to surface, shut off 5½ casing at 3982, pulled casing, placed rock bridge from 250' to 240', placed 10 sacks cement from 240' to 220', mudded to 20', set rock bridge to 15' and 5 sacks of cement in top of surface casing, which was cut off below plow depth. Location was cleared and leveled.

P&A Oil well

AJJ	
DVR	
FJK	
WIS	
HHH	
AH	
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date NOV 13 1957

Director

Company Walter S. Pendleton, Jr. Date 11/4/57Address Shamrock, Texas

Phone No. _____

By

(Signature)

Title

owner

P&A oil well