

Lease & Well No.	<b>Fee 13</b>
Company	Scout Energy Partners
Field Name	Rangely
Location	NESE, S28, T02N, R102W
Short Name	FEE013
County & State	Rio Blanco, CO
API No.	05-103-06226
Updated by	Jared Ede
Date of Diagram	4/2/2024
Kelly Bushing	5,288'
Ground Level	5,277'
Spud Date:	7/25/1946
Completion Date:	7/28/1946
Upper Perf	5,759'
Lower Perf	6,398'

Surface Casing							
Size	10 3/4"	Weight	40.5#	Grade	J-55	Depth	0'-977'
Year	1946	Sx. Cmt.	650 sx	Circulate		TOC @	

Production Casing							
Size	7"	Weight	23.#	Grade	J-55	Depth	0'-5,753'
Size		Weight		Grade		Depth	
Size		Weight		Grade		Depth	
Year	1946	Sx. Cmt.	1250 sx	Circulate		TOC @	

Production Liner							
Size	5"	Weight	18.#	Grade	L-80	Depth	5,598'-6,419'
Size		Weight		Grade		Depth	
Year	1984	Sx. Cmt.	200 sx	Circulate		TOC @	

