


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompletion ☐Notice of Intention to Abandon Well ☒Other ☐

(Check appropriate space)

LEASE NAME State "A" WELL NO. 1
FIELD Cotton Valley WILDCAT COUNTY Weld
LOCATION NW NW Section 16 Township 9N Range 56W Meridian 6th Princ.
(Quarter Quarter)
660 feet from N Section Line and 330 feet from W Section Line
N or S E or W

(DETAILS OF WORK)

9 5/8" casing cemented at 160' w/125 sx.

5 1/2" casing cemented at 5860' w/250 sx., perforated 5773'-5779'. PBTD 5781'.

Well incapable of producing. Will place 20 sx cement plug 5781'-5650'. Cut and pull 5 1/2" casing from lowest free point. Fill hole w/mud, place 10 sack plug in base of surface casing, plug top of surface casing with 5 sack plug. Cut off below ground level.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

OCT 11 1961

Date

Director

Company Consolidated Oil & Gas, Inc. Date 10-10-61Address 2112 Tower Bldg., Denver Phone No. AM 6-1306By [Signature] Title Chief Engineer
(Signature)