



DRILLER'S WELL LOG

COMPANY: Lonnie Gage, W. T. Hudson &
Strain Drilling CompanyC-SE-SE, Sec. 9, CONSERVATION COMMISSION
Twp. 9N, Rge. 56W,
Weld County, Colorado

OIL & GAS

LEASE: Nicklas

0	160 Surface
160	870 Shale
870	2120 Shale
2120	3020 Shale w/bentonite
3020	3615 Shale
3615	4145 Shale
4145	4480 Shale
4480	4710 Shale
4710	4933 Shale
4933	5020 Shale
5020	5220 Shale
5220	5326 Shale & lime
5326	5456 Shale & lime
5456	5660 Shale & lime
5660	5706 Shale
5706	5717 Shale
5717	5730 Shale
5730	5749 Shale
5749	5761 Sand
5761	5778 Sand & shale
5778	5827 Shale
5827	5840 Sand
5840	5858 Sand
5858	5867 Sand
5867	5892 Sand
5892	5895 Shale & sand
5895	Total Depth

COMMENCED: 7-14-56
COMPLETED: 7-23-56CASING RECORD:8-5/8" surface casing set @ 160'
W/90 sks. cement.CORING POINTS:

Core #1	5706' - 5730'	24'
J-Sand	5832' - 5872'	40'
Footage Cored		64'

DST'S:#1 5737' - 5761'
Tool open 1 hr., shut in 20 min.
Recovered 40' oil cut mud, 160'
mud cut water. FP-0-100#, SIP-1300#.LOGS:

E. S. & Micro Logs run to total depth.

GEOLOGIST:

Bill Hudson

ELEVATION: 4477' K. B.
NOTE: All meas. Kelly Bushing


TOPS	GEOLOGICAL			
Niobrara	4916	(-439)	Greenhorn	5496 (-1019)
Fort Hays	5220	(-743)	D-Sand	5748 (-1271)
Carlisle	5275	(-798)	J-Sand	5836 (-1359)
	Total Depth	5895		(-1418)

STATE OF COLORADO)
CITY & COUNTY OF DENVER) SSI hereby affirm that the above and foregoing is a
true and correct copy of the log of the Nicklas, located C-SE-SE, Section 9,
Township 9N, Range 56W, Weld County, Colorado.CONTRACTOR: STRAIN DRILLING COMPANYBY: T. C. Strain
T. C. StrainSubscribed and sworn to before me this 25th day of July, 1956

My Commission expires April 26, 1959

W. J. Kanda
Notary Public

**COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS**



(Indicate nature of data by checking below)

OIL & GAS
CONSERVATION COMMISSION

Notice of intention to drill (attach plat) _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____ **XX**
 Report of work done on well since previous report _____

Locate Well Correctly

C-SE-SE, Sec. 9, Twp. 9N, Range 56W, Weld County, Colorado			
9			

Notice to do work ☐
 Report of work done ☒

Land: Fee and Patented ☒
 State ☐

Lease No. _____

Colorado
State

Weld
County

Wildcat
Field

1 (Well No.) Nicklas (Lease) SE (1/4 Sec.) 9 (Sec.) 9N (Twp.) 56W (Range) 6 P. M. (Meridian)

The Well is located 660 Ft. (N) of Section Line and 660 Ft. **XX** of
 Section Line. **XX** (W)

The elevation above sea level is 4477 Ft. K. B.

Details of Plan of Work: (State names of and expected depths to objective sands.
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
 points, and all other important proposed work.)

"PLUGGING REPORT"

Filled hole with heavy mud to bottom of surface casing set at 160', placed wood
 plug, 1/2 sk. hulls and 30 sks. of cement @ 155'. Placed wood plug, 1/2 sk. hulls
 and 15 sks. of cement @ 40'--filling surface casing with cement to 2' below
 ground level.

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

Approved: JUL 26 1956

Date July 23, 1956

Company R. L. Gage, & W. T. Hudson

Address 1010 Midland Savings Building

CONTRACTOR By: T. C. Strain

Title Owner

Submit reports of proposed work, for approval, on this form, in Duplicate for patented
 lands and in Triplicate for school and state lands.

Subscribed and sworn to before me this 25th day of July, 1956

My Commission expires April 26, 1959

Mary Kanas
Notary Public