



# Howard's Casing Pulling

20617 County Rd 48  
Sterling, Colorado 80751  
(970) 522-8291

Sold Magpie Operating Inc.  
To: 11138 Wildhorse Peak.  
Littleton, Co. 80127

Date 5/19/97

Lease Cabene State # 1

Inv.# 3

Pulled rod and tubing.  
Plugged and abandoned well.

As per bid

\$1200.00

\$5000.00

\$6200.00

DATE	DAY WORK	REMARKS
05/12/97	0 hours	Moved rig on well. Raised mast. Rigged up on rod. Worked pump loose and pulled rod.
05/13/97	0 hours	Rigged up tongs on 2 7/8" tubing. Pulled tubing. Dug cellar. Had CIBP set by Bran-Dex at 5320'.
05/14/97	0 hours	Welded on collar on 5 1/2" Set in jacks and worked to 46" loaded hole. Pumped 2 sacks of cement on CIBP.
05/15/97	0 hours	Shot at 4400' and 4200' Worked loose and pulled 72 joints.
05/16/97	0 hours	Pulled out casing. Ran 2 7/8" tubing to 850'. Pumped 40 sacks cement. Pulled 2 7/8" to 200' and pumped 40 sacks cement. Pulled out 2 7/8"
05/19/97	0 hours	Set 10 sacks cement in top of 8 5/8" Cut off 8 5/8" down to 4' and welded on cap. Lowered mast.  Well complete.  Thank You.