

State of Colorado  
Energy & Carbon Management Commission1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

403697635

Receive Date:

02/25/2024

Report taken by:

RICK ALLISON

## Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by ECOM is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Closure request is not available for an Initial Site Investigation and Remediation Workplan.

## OPERATOR INFORMATION

|                                      |                             |                       |
|--------------------------------------|-----------------------------|-----------------------|
| Name of Operator: NOBLE ENERGY INC   | Operator No: 100322         | Phone Numbers         |
| Address: 1099 18TH STREET SUITE 1500 |                             | Phone: (970) 730-7281 |
| City: DENVER                         | State: CO                   | Zip: 80202            |
| Contact Person: Dan Peterson         | Email: rbueuf27@chevron.com | Mobile: ( )           |

## PROJECT, PURPOSE &amp; SITE INFORMATION

## PROJECT INFORMATION

Remediation Project #: 24600 Initial Form 27 Document #: 403091614

## PURPOSE INFORMATION

- ☐ Rule 913.c.(1): Pit or Cuttings Trench closure.
- ☐ Rule 913.c.(2): Buried or partially buried vessel closure, which will be by removal.
- ☒ Rule 913.c.(3): Remediation of Spill and Releases pursuant to Rule 912.
- ☐ Rule 913.c.(4): Land treatment of Oily Waste pursuant to Rule 905.e.
- ☐ Rule 913.c.(5): Closure of Centralized E&P Waste Management Facilities pursuant to Rule 907.h.
- ☐ Rule 913.c.(6): Remediation of impacted Groundwater pursuant to Rule 915.e.(3).D, and the contaminant concentrations in Table 915-1.
- ☐ Rule 913.c.(7): Investigation and remediation of natural gas in soil or Groundwater.
- ☐ Rule 913.c.(8): When requested by the Director due to any potential risk to soil, Groundwater, or surface water.
- ☒ Rule 913.c.(9): Decommissioning of Oil and Gas Facilities.
- ☐ Rule 913.g: Changes of Operator.
- ☐ Rule 915.b: Request to leave elevated inorganics in situ.
- ☐ Other: \_\_\_\_\_

## SITE INFORMATION

Yes Multiple Facilities

|  |                     |                        |  |
|--|---------------------|------------------------|--|
| Facility Type: WELL                            | Facility ID: _____  | API #: 123-24009       | County Name: WELD                        |
| Facility Name: FRENZEL B 15-25                 | Latitude: 40.395921 | Longitude: -104.540770 |  |
| ** correct Lat/Long if needed: Latitude: _____ |                     | Longitude: _____       |  |
| QtrQtr: NWSW                                   | Sec: 15             | Twp: 5N                | Range: 6W Meridian: 6 Sensitive Area? No |

## SITE CONDITIONS

General soil type - USCS Classifications SW Most Sensitive Adjacent Land Use grassland

Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? No

**Other Potential Receptors within 1/4 mile**

HPH N  
Freshwater Emergent Wetlands 0.04/0.1mi NW, 0.05/0.17mi W, 0.05mi S  
Freshwater Pond 0.05/0.23mi NW  
Riverine 0.13mi NW  
Structure 0.19mi NW

**SITE INVESTIGATION PLAN****TYPE OF WASTE:**

☒ **E&P Waste** ☐ **Other E&P Waste** ☐ **Non-E&P Waste**

☒ Produced Water

☐ Workover Fluids

☒ Oil

☐ Tank Bottoms

☐ Condensate

☐ Pigging Waste

☐ Drilling Fluids

☐ Rig Wash

☐ Drill Cuttings

☐ Spent Filters

☐ Pit Bottoms

☐ Other (as described by EPA)

**DESCRIPTION OF IMPACT**

| Impacted? | Impacted Media | Extent of Impact | How Determined      |
|-----------|----------------|------------------|---------------------|
| Yes       | GROUNDWATER    | Unknown          | laboratory analysis |
| Yes       | SOILS          | Unknown          | laboratory analysis |

**INITIAL ACTION SUMMARY**

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

Pursuant to COGCC Rule 911 a site investigation will be conducted pertaining to the FRENZEL B15-25 wellhead cut and cap and flowline removal. Approximately 742' of flowline will be removed. The wellhead was cut and capped per COGCC rules. Additionally, soil samples were collected at any points of material change and/or hammer unions, directional changes, as well as at the bell holes on either side of a waterway, AS APPLICABLE to abandonment type. The Flowline Pre-Abandonment Notice Document number was previously included under Related Forms.

**PROPOSED SAMPLING PLAN****Proposed Soil Sampling**

☒ Will soil samples be collected as part of this investigation? ( Number, type (grab/composite), analyses, and locations of samples ):

A grab soil sample was collected at the base of the excavation or the area showing the highest degree of impact during field screening activities at the wellhead excavation. Additionally, soil samples were collected along the flowline at any points of material change and/or hammer unions, directional changes, as well as at the bell holes on either side of a waterway, AS APPLICABLE to abandonment type. A grab confirmation soil sample was collected at the wellhead excavation. Soil samples were analyzed by a certified laboratory for TPH (total volatile [C6-C10] and extractable [C10-C36] hydrocarbons) organic compounds in soil per ECMC Table 915-1, and EC, SAR, pH, and boron. All samples collected were analyzed by a certified laboratory using approved ECMC laboratory analysis methods.

**Proposed Groundwater Sampling**

☒ Will groundwater samples be collected as part of this investigation? ( Number, analyses, and locations of samples ):

Groundwater was encountered during the site investigation. See attached for details

**Proposed Surface Water Sampling**

☐ Will surface water samples be collected as part of this investigation? ( Number, analyses, and locations of samples ):

**Additional Investigative Actions**

☐ Additional alternative investigative actions described in attached Site Investigation Plan ( summary ):

Visual inspection along the flowline and at the wellhead and separator areas occurred during abandonment activities. Field personnel field screened all disturbed areas using visual and olfactory senses to determine if laboratory confirmation sampling was required. The applicable ECMC Closure Checklists were utilized and filled out during the abandonment process. A photolog is attached.

# SITE INVESTIGATION REPORT

## SAMPLE SUMMARY

### Soil

Number of soil samples collected 10

Number of soil samples exceeding 915-1 3

Was the areal and vertical extent of soil contamination delineated? No

Approximate areal extent (square feet) 200

### NA / ND

-- Highest concentration of TPH (mg/kg) 74

-- Highest concentration of SAR 9.57

BTEX > 915-1 No

Vertical Extent > 915-1 (in feet) 3

### Groundwater

Number of groundwater samples collected 3

Was extent of groundwater contaminated delineated? No

Depth to groundwater (below ground surface, in feet) 3

Number of groundwater monitoring wells installed 0

Number of groundwater samples exceeding 915-1 1

-- Highest concentration of Benzene (µg/l) 32.5

-- Highest concentration of Toluene (µg/l) 39.4

-- Highest concentration of Ethylbenzene (µg/l) 7.06

-- Highest concentration of Xylene (µg/l) 46.1

NA Highest concentration of Methane (mg/l)

### Surface Water

0 Number of surface water samples collected

Number of surface water samples exceeding 915-1

If surface water is impacted, other agency notification may be required.

## OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☒ Were background samples collected as part of this site investigation?

One background sample was collected from an area not impacted by oil and gas development at similar depths and lithologies as confirmation samples collected at the Frenzel wellhead location and analyzed for ECMC Table 915-1 metals and soil suitability for reclamation standards (EC, SAR, and Boron) and metals.

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards)

Volume of liquid waste (barrels)

☒ Is further site investigation required?

See Remedial Action Plan.

## REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No

## SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Impacted soil will be removed from the release area at the Frenzel wellhead and along the flowline by excavation. The impacted soil will be disposed of at an approved landfill as non-hazardous waste in accordance with Rules 905 and 906. Copies of the waste manifests will be available upon request.

## REMEDIAL SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Before excavation of impacted soil, soil borings will be installed to delineate the vertical and lateral extent of soil impacts at the location. Confirmation soil samples will be collected and analyzed for the full Table 915 suite. If groundwater is encountered, the soil boring(s) will be improved with temporary PVC monitoring wells and sampled for Table 915 constituents in groundwater.

If groundwater impacts are observed, an NFA will be requested once four consecutive quarters of groundwater sampling have been completed and reported at the location with concentrations of Table 915 constituents below regulatory limits. As needed, soil and/or groundwater remediation plans will be developed and submitted to ECMC in a supplemental Form 27.

Should no additional active remediation be required following source removal at the location, a no further action (NFA) determination will be requested within 90 days following laboratory confirmation of the removal of impacted soils with respect to the applicable Table 915-1 screening levels at the site.

## Soil Remediation Summary

☐ In Situ

\_\_\_\_\_ Bioremediation ( or enhanced bioremediation )  
\_\_\_\_\_ Chemical oxidation  
\_\_\_\_\_ Air sparge / Soil vapor extraction  
\_\_\_\_\_ Natural Attenuation  
\_\_\_\_\_ Other \_\_\_\_\_

☐ Ex Situ

\_\_\_\_\_ Excavate and offsite disposal  
\_\_\_\_\_ If Yes: Estimated Volume (Cubic Yards) \_\_\_\_\_  
\_\_\_\_\_ Name of Licensed Disposal Facility or ECMC Facility ID # \_\_\_\_\_  
\_\_\_\_\_ Excavate and onsite remediation  
\_\_\_\_\_ Land Treatment  
\_\_\_\_\_ Bioremediation (or enhanced bioremediation)  
\_\_\_\_\_ Chemical oxidation  
\_\_\_\_\_ Other \_\_\_\_\_

## Groundwater Remediation Summary

\_\_\_\_\_ Bioremediation ( or enhanced bioremediation )  
\_\_\_\_\_ Chemical oxidation  
\_\_\_\_\_ Air sparge / Soil vapor extraction  
\_\_\_\_\_ Natural Attenuation  
\_\_\_\_\_ Other \_\_\_\_\_

## GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

A minimum of five groundwater monitoring wells will be installed as to delineate the magnitude and extent of groundwater impacts. The samples will be analyzed by a certified laboratory for the full suite of ECMC Table 915-1 organics and inorganics. The wells will be monitored quarterly until four consecutive quarters of ECMC Table 915-1 compliant groundwater concentrations are achieved.

## REMEDIATION PROGRESS UPDATE

### PERIODIC REPORTING

#### Approved Reporting Schedule:

☒ Quarterly☐ Semi-Annually☐ Annually☐ Other

#### ☐ Request Alternative Reporting Schedule:

☐ Semi-Annually☐ Annually☐ Other

Rule 913.e:

After initial approval of a Form 27, the Operator will provide quarterly update reports in a Supplemental Form 27 to document progress of site investigation and remediation, unless an alternative reporting schedule has been requested by the Operator and approved by the Director. The Director may request a more frequent reporting schedule based on site-specific conditions.

#### Report Type:

☐ Groundwater Monitoring☐ Land Treatment Progress Report☐ O&M Report☒ Other Supplemental Form 27

### Adequacy of Operator's General Liability Insurance and Financial Assurance

Describe the adequacy of the Operator's general liability insurance and Financial Assurance to fully address the anticipated costs of Remediation, including the estimated remaining cost for this project (below).

If this information has been provided on a Form 27 within the last 12 months, provide the Document Number of that form.

Noble intends to directly address the costs of remediation at the locations as part of our asset retirement obligation process and operations. Noble has general liability insurance (policy MWZZ 316714) and financial assurance in compliance with ECMC rules. Records are available on the ECMC's website. The cost for remediation is an estimate only, costs may change upwards or downward based on site-specific information. Noble makes no representation or guarantees as to the accuracy of the estimate.

Operator anticipates the remaining cost for this project to be: \$ 70000

### WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? No

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

Volume of E&P Waste (solid) in cubic yards

E&P waste (solid) description

ECMC Disposal Facility ID #, if applicable:

Non-ECMC Disposal Facility:

Volume of E&P Waste (liquid) in barrels

E&P waste (liquid) description

ECMC Disposal Facility ID #, if applicable:

Non-ECMC Disposal Facility:

## REMEDIATION COMPLETION REPORT

### REMEDIATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No

If YES:

☐ Compliant with Rule 913.h.(1).☐ Compliant with Rule 913.h.(2).☐ Compliant with Rule 913.h.(3).

Do all soils meet Table 915-1 standards? No

Does the previous reply indicate consideration of background concentrations?

Does Groundwater meet Table 915-1 standards? No

Is additional groundwater monitoring to be conducted? Yes

Operator shall comply with the ECMC 1000-Series Reclamation Requirements for all impacted and disturbed areas.

## RECLAMATION PLAN

### RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

Reclamation will be in accordance with COGCC 1000 Series Rules.

Is the described reclamation complete? No

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim

☐ Final

Did the Surface Owner provide the seed mix? \_\_\_\_\_

If YES, does the seed mix comply with local soil conservation district recommendations? \_\_\_\_\_

Did the local soil conservation district provide the seed mix? \_\_\_\_\_

### SITE RECLAMATION DATES

Proposed date of commencement of Reclamation. \_\_\_\_\_

Proposed date of completion of Reclamation. \_\_\_\_\_

## IMPLEMENTATION SCHEDULE

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

### PRIOR DATES

Date of Surface Owner notification/consultation, if required. 06/07/2022

Actual Spill or Release date, or date of discovery. \_\_\_\_\_

### SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). \_\_\_\_\_

Proposed site investigation commencement. 07/15/2022

Proposed completion of site investigation. 12/07/2022

### REMEDIAL ACTION DATES

Proposed start date of Remediation. 12/07/2022

Proposed date of completion of Remediation. 12/06/2024

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

☐ Change from approved implementation schedule per Rule 913.d.(2).

Basis for change in implementation schedule:

**OPERATOR COMMENT**

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Ethan Black

Title: Consultant

Submit Date: 02/25/2024

Email: ethanb@fremontenv.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with ECMC Rules and applicable orders and is hereby approved.

ECMC Approved: RICK ALLISON

Date: 04/09/2024

Remediation Project Number: 24600

**COA Type****Description**

|        |  |
|--------|--|
|        | Operator shall conducted proposed site assessment within 90 days and continue quarterly reporting.   |
|        | Background sample appears to have been collected from within the former well pad. Additional background samples shall be collected from areas outside the original oil and gas location disturbance.   |
|        | Groundwater impacts were documented at the well. A minimum of four quarters of post-remediation groundwater monitoring is required. Groundwater samples shall be analyzed for Table 915-1 Organic Compounds in Groundwater and Groundwater Inorganic Parameters. |
| 3 COAs |  |

**ATTACHMENT LIST**

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

**Att Doc Num****Name**

|           |  |
|-----------|--|
| 403697635 | INVESTIGATION/REMEDATION WORKPLAN (SUPPLEMENTAL) |
| 403697636 | OTHER  |
| 403697637 | OTHER  |
| 403697638 | OTHER  |
| 403747515 | FORM 27-SUPPLEMENTAL-SUBMITTED                   |

Total Attach: 5 Files

**General Comments****User Group****Comment****Comment Date**

|  |  |                     |
|--|--|---------------------|
|  |  | Stamp Upon Approval |
|--|--|---------------------|

Total: 0 comment(s)