

State of Colorado
Energy & Carbon Management Commission1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

403726186

Receive Date:

03/20/2024

Report taken by:

RICK ALLISON

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by ECMC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Closure request is not available for an Initial Site Investigation and Remediation Workplan.

OPERATOR INFORMATION

Name of Operator: NOBLE ENERGY INC	Operator No: 100322	Phone Numbers Phone: (970) 730-7281 Mobile: ()
Address: 1099 18TH STREET SUITE 1500		
City: DENVER	State: CO Zip: 80202	
Contact Person: Dan Peterson	Email: rbueuf27@chevron.com	

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 25436 Initial Form 27 Document #: 403184619

PURPOSE INFORMATION

- ☐ Rule 913.c.(1): Pit or Cuttings Trench closure.
- ☐ Rule 913.c.(2): Buried or partially buried vessel closure, which will be by removal.
- ☒ Rule 913.c.(3): Remediation of Spill and Releases pursuant to Rule 912.
- ☐ Rule 913.c.(4): Land treatment of Oily Waste pursuant to Rule 905.e.
- ☐ Rule 913.c.(5): Closure of Centralized E&P Waste Management Facilities pursuant to Rule 907.h.
- ☐ Rule 913.c.(6): Remediation of impacted Groundwater pursuant to Rule 915.e.(3).D, and the contaminant concentrations in Table 915-1.
- ☐ Rule 913.c.(7): Investigation and remediation of natural gas in soil or Groundwater.
- ☐ Rule 913.c.(8): When requested by the Director due to any potential risk to soil, Groundwater, or surface water.
- ☒ Rule 913.c.(9): Decommissioning of Oil and Gas Facilities.
- ☐ Rule 913.g: Changes of Operator.
- ☐ Rule 915.b: Request to leave elevated inorganics in situ.
- ☐ Other: _____

SITE INFORMATION

No Multiple Facilities

Facility Type: WELL	Facility ID: _____	API #: 123-25729	County Name: WELD
Facility Name: PATRIOT B 16-20	Latitude: 40.399252	Longitude: -104.559793	
** correct Lat/Long if needed: Latitude: _____		Longitude: _____	
QtrQtr: NWSW	Sec: 16	Twp: 5N	Range: 6W Meridian: 6 Sensitive Area? Yes

SITE CONDITIONS

General soil type - USCS Classifications SW Most Sensitive Adjacent Land Use Crop Land

Is domestic water well within 1/4 mile? No Is surface water within 1/4 mile? No

Is groundwater less than 20 feet below ground surface? No

Other Potential Receptors within 1/4 mile

Irrigation Ditches 0.01mi N, 0.24mi W, 0.03mi E, 0.15/0.16mi SE

SITE INVESTIGATION PLAN**TYPE OF WASTE:**☒ **E&P Waste** ☐ **Other E&P Waste** ☐ **Non-E&P Waste**☒ Produced Water☐ Workover Fluids☒ Oil☐ Tank Bottoms☐ Condensate☐ Pigging Waste☐ Drilling Fluids☐ Rig Wash☐ Drill Cuttings☐ Spent Filters☐ Pit Bottoms☐ Other (as described by EPA)**DESCRIPTION OF IMPACT**

Impacted?	Impacted Media	Extent of Impact	How Determined
No	GROUNDWATER	NA	Lab analysis if encountered
Yes	SOILS	See attached	Lab analysis

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

Pursuant to COGCC Rule 911 a site investigation was conducted pertaining to the PATRIOT B16-20 wellhead cut and cap and flowline removal. Approximately 2452' of flowline was removed. The wellhead was cut and capped per ECMC rules. Additionally, soil samples were collected at any points of material change and/or hammer unions, directional changes, as well as at the bell holes on either side of a waterway, AS APPLICABLE to abandonment type. The Flowline Pre-Abandonment Notice Document number is included under Related Forms.

PROPOSED SAMPLING PLAN**Proposed Soil Sampling**☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Grab confirmation soil samples were collected along the flowline at any points of material change and/or hammer unions, directional changes, as well as at the bell holes on either side of a waterway, AS APPLICABLE to abandonment type. Soil samples were analyzed by a certified laboratory for TPH (total volatile [C6-C10] and extractable [C10-C36] hydrocarbons) organic compounds in soil per ECMC Table 915-1, and EC, SAR, pH, and boron. All samples collected were analyzed by a certified laboratory using approved ECMC laboratory analysis methods. A grab confirmation soil sample will be collected at the wellhead excavation in base of the excavation or the area showing the highest degree of impact during field screening activities at the wellhead excavation. The ECMC will be updated with the results of the wellhead decommissioning activities on a supplemental F27.

Proposed Groundwater Sampling☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Groundwater was not encountered during the site investigation.

Proposed Surface Water Sampling☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):**Additional Investigative Actions**☐ Additional alternative investigative actions described in attached Site Investigation Plan (summary):

Visual inspection of the wellhead and flowline areas occurred during abandonment activities. Field personnel field screened all disturbed areas using visual and olfactory senses to determine if laboratory confirmation sampling was required. The applicable ECMC Closure Checklists were utilized and filled out during the abandonment process. A photolog is attached.

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 4

Number of soil samples exceeding 915-1 2

Was the areal and vertical extent of soil contamination delineated? No

Approximate areal extent (square feet) 400

NA / ND

Highest concentration of TPH (mg/kg)

-- Highest concentration of SAR 1.19

BTEX > 915-1 No

Vertical Extent > 915-1 (in feet) 3

Groundwater

Number of groundwater samples collected 0

Was extent of groundwater contaminated delineated? No

Depth to groundwater (below ground surface, in feet)

Number of groundwater monitoring wells installed

Number of groundwater samples exceeding 915-1

Highest concentration of Benzene (µg/l)

Highest concentration of Toluene (µg/l)

Highest concentration of Ethylbenzene (µg/l)

Highest concentration of Xylene (µg/l)

Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected

Number of surface water samples exceeding 915-1

If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☐ Were background samples collected as part of this site investigation?

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards)

Volume of liquid waste (barrels)

☐ Is further site investigation required?

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Impacted soil was removed from the release area at the Patriot B 16-20 flowline location by excavation. The impacted soil was disposed of at an approved landfill as non-hazardous waste in accordance with Rules 905 and 906. Copies of the waste manifests will be available upon request.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Excavation of impacted soil was undertaken to remove impacts observed three feet below ground surface along the Patriot B 16-20 flowline. Confirmation soil samples were collected and analyzed for ECMC Table 915 organic and Soil Suitability for Reclamation constituents (TPH, BTEX, 1,2,4 Trimethylbenzene, 1,3,5 Trimethylbenzene, Naphthalene, Polycyclic Aromatic Hydrocarbons [PAHs], pH, SAR, EC, and Boron) and ECMC Table 915-1 metals. Excavation activities are detailed in the attached.

The operator is requesting application of the RSSLs based on a greater than 30 feet separation between the excavation's maximum depth of two feet bgs and a depth to water of 43 feet bgs demonstrating the improbability for communication between groundwater and historical hydrocarbon impacts at the Patriot location. The operator proposes to address residual elevated metals concentrations (arsenic, barium, selenium) at the former separator location and pH at the flowline FL08 bellhole location with a reclamation plan submitted with a additional supplemental Form 27.

Should no additional active remediation be required following findings of the reclamation plan, a no further action (NFA) determination will be requested.

Soil Remediation Summary

☐ In Situ

_____ Bioremediation (or enhanced bioremediation)

_____ Chemical oxidation

_____ Air sparge / Soil vapor extraction

_____ Natural Attenuation

_____ Other _____

☒ Ex Situ

Yes _____ Excavate and offsite disposal

_____ If Yes: Estimated Volume (Cubic Yards) _____ 10

_____ Name of Licensed Disposal Facility or ECMC Facility ID # _____

_____ Excavate and onsite remediation

_____ Land Treatment

_____ Bioremediation (or enhanced bioremediation)

_____ Chemical oxidation

_____ Other _____

Groundwater Remediation Summary

_____ Bioremediation (or enhanced bioremediation)

_____ Chemical oxidation

_____ Air sparge / Soil vapor extraction

_____ Natural Attenuation

_____ Other _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

NA

REMEDIATION PROGRESS UPDATE

PERIODIC REPORTING

Approved Reporting Schedule:

☒ Quarterly☐ Semi-Annually☐ Annually☐ Other

☐ Request Alternative Reporting Schedule:

☐ Semi-Annually☐ Annually☐ Other

Rule 913.e:

After initial approval of a Form 27, the Operator will provide quarterly update reports in a Supplemental Form 27 to document progress of site investigation and remediation, unless an alternative reporting schedule has been requested by the Operator and approved by the Director. The Director may request a more frequent reporting schedule based on site-specific conditions.

Report Type:

☐ Groundwater Monitoring☐ Land Treatment Progress Report☐ O&M Report☒ Other Supplemental Form 27

Adequacy of Operator's General Liability Insurance and Financial Assurance

Describe the adequacy of the Operator's general liability insurance and Financial Assurance to fully address the anticipated costs of Remediation, including the estimated remaining cost for this project (below).

If this information has been provided on a Form 27 within the last 12 months, provide the Document Number of that form.

Noble intends to directly address the costs of remediation at the locations as part of our asset retirement obligation process and operations. Noble has general liability insurance (policy MWZZ 316714) and financial assurance in compliance with ECMC rules. Records are available on the ECMC's website. The cost for remediation is an estimate only, costs may change upwards or downward based on site-specific information. Noble makes no representation or guarantees as to the accuracy of the estimate.

Operator anticipates the remaining cost for this project to be: \$ 5000

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? No

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

No beneficial use

Volume of E&P Waste (solid) in cubic yards 10

E&P waste (solid) description hydrocarbon impacted soil

ECMC Disposal Facility ID #, if applicable:

Non-ECMC Disposal Facility: Buffalo Ridge Landfill, Keenesburg, CO

Volume of E&P Waste (liquid) in barrels 0

E&P waste (liquid) description

ECMC Disposal Facility ID #, if applicable:

Non-ECMC Disposal Facility:

REMEDIATION COMPLETION REPORT

REMEDIATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No

If YES:

☐ Compliant with Rule 913.h.(1).

☐ Compliant with Rule 913.h.(2).

☐ Compliant with Rule 913.h.(3).

Do all soils meet Table 915-1 standards? No

Does the previous reply indicate consideration of background concentrations?

Does Groundwater meet Table 915-1 standards? Yes

Is additional groundwater monitoring to be conducted? _____

Operator shall comply with the ECMC 1000-Series Reclamation Requirements for all impacted and disturbed areas.

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

Reclamation will be in accordance with COGCC 1000 Series Rules.

Is the described reclamation complete? No

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim

☐ Final

Did the Surface Owner provide the seed mix? _____

If YES, does the seed mix comply with local soil conservation district recommendations? _____

Did the local soil conservation district provide the seed mix? _____

SITE RECLAMATION DATES

Proposed date of commencement of Reclamation. _____

Proposed date of completion of Reclamation. _____

IMPLEMENTATION SCHEDULE

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

PRIOR DATES

Date of Surface Owner notification/consultation, if required. 08/17/2022

Actual Spill or Release date, or date of discovery. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). _____

Proposed site investigation commencement. 10/15/2022

Proposed completion of site investigation. 02/10/2023

REMEDIAL ACTION DATES

Proposed start date of Remediation. 02/20/2023

Proposed date of completion of Remediation. 12/31/2024

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

☒ Change from approved implementation schedule per Rule 913.d.(2).

Basis for change in implementation schedule:

A reclamation plan is proposed to address residual elevated concentrations of metals and pH. Pending location landowner approval and contractor availability, the operator will complete a reclamation plan as outlined in the proposed remediation workplan.

OPERATOR COMMENT

Excavation activities related to the flowline and tank battery are detailed in the attached. Since additional remediation is need at both locations the operator is proposing to consolidate reporting of all further remediation activities relating to the Patriot B16-20 flowline Rem.# 25436 to the Patriot B65N64W tank battery Rem. # 25418.

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Ethan Black

Title: Consultant

Submit Date: 03/20/2024

Email: ethanb@fremontenv.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with ECMC Rules and applicable orders and is hereby approved.

ECMC Approved: RICK ALLISON

Date: 04/09/2024

Remediation Project Number: 25436

COA Type**Description**

	Operator did not adhere to approved Initial Form 27 workplan for flowline assessment. Operator shall submit a Supplemental Form 27 within 30 days (by May 9, 2024) with a plan and schedule for assessment of the abandoned in place flowline.
	Operator's background samples from separator excavation appear influenced by oil and gas activity and may not be valid for the purposes of establishing background. However, background collected near excavation at the flowline (Spill 483970) may be considered. In addition, Operator's statement regarding addressing arsenic, barium and selenium at the former separator location is unclear. Operator shall re-interpret background conditions and confirmation soil sample results in light of the invalid background samples and propose any required additional assessment or remediation in a Supplemental Form 27.
	ECMC agrees to consolidate Spill 483969 under Remediation 25418 as reported on Form 19 Doc# 403333886. Spill 483970 shall continue under Remediation 25436 along with additional required flowline assessment.
3 COAs	

ATTACHMENT LIST

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num**Name**

403726186	FORM 27-SUPPLEMENTAL-SUBMITTED
403726287	OTHER

Total Attach: 2 Files

General Comments**User Group****Comment****Comment Date**

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)