

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

RECEIVED  
AUG 23 1957  
OIL & GAS  
CONSERVATION COMMISSION



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplate	<input type="checkbox"/>	Report of Remedial Work	<input checked="" type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Fred Brunner WELL NO. 2  
 FIELD New Windsor WILDCAT COUNTY Weld  
 LOCATION NE, SW Section 26 Township 7N Range 67W Meridian 6th PM  
 (Quarter Quarter)  
~~861~~ feet from N 5 Section Line and 1981 feet from W Section Line  
 1983 N or S E or W

(DETAILS OF WORK)

This well was treated with a bradenhead sand-oil-squeeze with 30,000 gallons gelled crude and 30,000# sand which was comprised of two equal batches separated by a temporary plugging agent. This was preceded by 50 bbls crude containing 25 bbls Hyflo. Batch #1 was injected at a 22 BPM rate at 2600 psi. Batch #2 was injected at a 22 to 15 BPM rate at 2600 psi to 3700 psi. Pressure went to zero in 5½ hours. Ran bit and cleaned out fillup from 8983' to PBD of 9026'. Production prior to remedial work 36 BOPD, cut 12% water. Production following job has leveled off at 140 BOPD, cut 20% water.

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED: AUG 23 1957 Date  
 Company The California Company Date 8/22/57  
 Address Box 1769, Casper, Wyoming Phone No. 2-5303  
 Director [Signature] By [Signature] Title Area Supt.