

NEW WINDSOR #1 VICTOR DENNY

RECEIVED

OGCC Form 4

OCT - 6 1969

COLO. OIL & GAS CONS. COMM.  
OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

## SUNDRY NOTICES AND REPORTS ON WELLS

## INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☒

Notice of Intention to Change Plans

☐

Report of Recompleation

☐

Notice of Intention to Abandon Well

☐

Other

☐

(Check appropriate space)

LEASE NAME Victor Denny WELL NO. 1FIELD New Windsor WILDCAT COUNTY WeldLOCATION NE SE Section 27 Township 7N Range 67W Meridian 6th P.M.  
(Quarter Quarter)1933 feet from S Section Line and 662 feet from E Section Line  
N or S E or W

## (DETAILS OF WORK)

Subject well was Bradenhead Sand Oil Squeezed with 30,000 gallons of crude and 30,000 lbs. sand as follows:

1. Filled tubing with 40 barrels crude containing 1/2 gallon Hy Flo per barrel.
2. Pumped sand oil into formation. Formation breakdown pressure 2000 psi. Maximum injection pressure 1800 psi. Overall injection rate 51 barrels per minute. Final standing pressure 2200 psi, going to zero in 20 hours.

The production from subject well, since the above sand oil squeeze, has leveled off at approximately 50 barrels oil per day, cutting 12% water. Production prior to the workover was 40 BOPD with a 4% water cut.

BEST IMAGE  
AVAILABLE

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Company The California Company Date November 7, 1957

Date

Address P.O. Box 1769, Casper, Wyo. Phone No. 2-5303

Director

By [Signature]  
(Signature)Title Area Supt.