




RECEIVED

OCT - 6 1969

COLO. OIL & GAS CONS. COMM.
OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplate	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input checked="" type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Victor Deany WELL NO. 1

FIELD New Windsor WILDCAT COUNTY Weld

LOCATION NE SE Section 27 Township 7N Range 67W Meridian 6th P.M.
(Quarter Quarter)

1983 feet from S Section Line and 662 feet from E Section Line
N or S E or W

(DETAILS OF WORK)

The Lyons formation was cored and found to be too tight for commercial production. This formation had a total measured permeability of only 2.7 MD. Total depth was 9098'. It is planned to plugback and run 7" casing to \pm 4300'. We will then perforate and sand oil squeeze the Sussex for a test of this formation. Approval of the following plug-back procedure was received from Mr. A. J. Jersin in phone conversation with R. L. Green on 2-22-57. This is to confirm the following procedure:

1. Set 50 sack Slocet cement plug in interval 8895'-9020' over top of Lyons.
2. Set 50 sack Slo-set cement plug in interval 7565'-7690' over top of Muddy.

Schlumberger tops as follows:

Sussex	4273'	(\pm 689')
Muddy	7675'	(-2713')
Lyons	9011'	(-4049')

BEST IMAGE
AVAILABLE

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED: FEB 23 1957 Company The California Company Date 2-25-57

Date Address P. O. Box 1769, Casper, Wyo. Phone No 2-5203

Director A. J. Jersin By R. L. Green Title Asst. Supt.
(Signature)