


COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS

CONSERVATION COMMISSION

BEST IMAGE (Indicate nature of data by checking below)
AVAILABLE

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____ **X**
 Report of work done on well since previous report _____

Following is a ~~(notice of intention to do work)~~ July 25, 1955 19
 (report of work done) (patented) described as follows:

Colorado Weld Wildcat
 State County Field
1 O. A. Nashland SW 1/4 24 7 North 67 West 6th P.M.
 (Well No.) (Lease) (Sec. and 1/4 Sec.) (Twp.) (Range) (Meridian)
 The well is located 660 ft. (N) of South and 660 ft. (E) of West
 (S) (W)

The elevation above sea level is 4993 KB ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Permission to plug was received from Mr. A. J. Jersin, July 24, 1955 by telephone
 Plugging procedure: Placed bottom plug in Muddy sand 35 sks. 7790-7700. Plug of 15 sks in bottom of 10-3/4" surface casing, 630'-600'; plug of 10 sks. in top of 10-3/4" surface casing and steel cap welded on top of surface pipe 30" below surface of cultivated field. Heavy mud was left in the hold between cement plugs. Cementing was done by Halliburton Oil Well Cementing Company, July 25, 1955.

AJJ	
DVR	
FJK	
OPS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

Approved: JUL 26 1955

Company JAMES P. SLOSS

Address 780 Denver Club Bldg., Denver, Col.

By Carl J. Kaelthli

Title Geologist

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.