

API#

123-054110

OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO

RECEIVED DEC 4 - 1963

OIL & GAS CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator The Clayton Oil Company Field New Raymer Wildcat
Lease Name Warrick Well No. 1 County Weld
Location NE/4 NW/4 Section 11 Township 7 North Range 58 West Meridian 6th
660 feet from North Section line and 1980 feet from West Section Line

TOTAL DEPTH 6360 DATE OF PLUGGING December 1, 1963

DETAILS OF WORK

Plugged from 6360 to 6250 feet with drilling mud, From 6250 feet to 6100 feet with 35 sks. cement, from 6100 feet to 100 feet with mud, From 100 feet to 80 feet with 15 sks. cement, from 80 feet to 15 feet with drilling mud, from 15 feet to top of surface with 10 sks. cement. Cut surface pipe off and weld cap on top.

Location checked on 7/28/64, OK Jim

Table with 2 columns and 6 rows: DVR, WRS, HHM, JAM, FJP, JJD, FILE. Checkmarks are present in the JAM, FJP, and JJD rows.

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: Date DEC 5 1963 Director [Signature]

Company The Clayton Oil Company Date December 3, 1963 Address 1840 First National Bank Bldg Denver, Colorado, 80202 Phone No. 222-9044 By [Signature] Title General Partner

