

Donnelly Casing Pulling Co.

Phone 522-1410

P.O. Box 791
Sterling, Colorado 80751



00204739

SOLD TO
Sunset Hill
c/o Mark R. Powell
10442 North 75th St.,
Longmont, CO 80503

WELL
Doll Estate

INVOICE DATE 3-06-90

INVOICE NO. 90-228

5498' 4 1/2" OD Casing @ \$ 1.25 per foot \$6872.50

RECEIVED PAYMENT 3-05-90 (\$6875.00)

(\$ 2.50)

DATE	DAY WORK	REMARKS
2-19-90	0 hours	Moved rig. Raised mast. Dug cellar and pit. Hooked up lines. Ran sand to 6250'.
2-20-90	0 hours	Raised poles. Set in jacks. Worked pipe to 8". Dumped 5 sacks cement on sand at 6250'.
2-22-90	0 hours	Started running tubing. Got in 35 joints. Started getting mud out.
2-23-90	0 hours	Ran 55 joints tubing. Pumped 150 bbls. water and mud. Spotted 20 bbls. oil. Pulled tubing.
2-26-90	0 hours	Worked pipe to 54". Shot at 5500'. Came loose. Pulled 15 joints.
2-27-90	0 hours	Pulled pipe to 1200'.
2-28-90	0 hours	Pumped 25 sacks cement at 1200'. Pulled out casing. Set 15 sacks cement half in and half out bottom of surface at 221', from 235' to 190'. Set 10 sacks cement in top of surface. Welded on cap.

WELL COMPLETE

THANK YOU

RECEIVED

APR 27 1990

COLO. OIL & GAS CONS. COMM.

All open accounts are due by 10th of month following purchase. All amounts 30 days past due will be charged a FINANCE CHARGE at 1 1/2% per month or an ANNUAL PERCENTAGE RATE of 18%.