

# Donnelly Casing Pulling Co.

Phone 522-1410

P.O. Box 791

Sterling, Colorado 80751

Bob Donnelly



00204720

RECEIVED

FEB 28 1991

SOLD  
TO

Sunset Hill  
c/o Mr. Mark Powell  
10442 North 75th St.  
Longmont, CO 80503

INVOICE DATE 12-13-90

WELL

Doll Estate #1

INVOICE NO. 91-109

COLO. OIL & GAS CONS. COMM.

DATE	DAY WORK	REMARKS
1200' 4½" OD Casing @		\$ 1.25 per foot \$1500.00
2-28-90	0 hours	Moved rig in. Raised mast. Ran sand to 6300'.
3-01-90	0 hours	Dug cellar. Set in jacks. Worked pipe to 12". Dumped 5 sacks cement on sand at 6300'. Loaded hole. Started running tubing.
3-02-90	0 hours	Ran 50 joints tubing. Had a hard time getting down. Lots of heavy mud.
3-03-90	0 hours	Pumped 100 bbls. water and mud to wash out casing. Spotted 20 bbls. oil. Pulled tubing.
3-05-90	0 hours	Worked pipe to 10".
3-06-90	0 hours	Worked pipe to 12".
3-08-90	0 hours	Worked pipe at 12".
3-12-90	0 hours	Ran 40 joints tubing. Pumped 200 bbls. mud.
3-13-90	0 hours	Pumped 150 bbls. mud around casing. Spotted 20 bbls. oil. Pump job.
3-14-90	0 hours	Pulled tubing. Worked pipe at 12". Dug pit.
3-15-90	0 hours	Worked pipe at 12". Shot at 5300'. Swabbed out casing.
3-19-90	0 hours	Worked pipe. Pulled in two down 12 joints. Lowered poles. Moved off.
11-16-90	0 hours	Moved rig on well. Raised mast. Dug cellar out.
11-19-90	0 hours	Rigged up floor. Started running fishing tool. Mud in hole. Couldn't get down casing.
11-20-90	0 hours	Washed out casing. Set fishing tool on casing. Worked pipe to 13". There was a plug in casing below fishing tool. Ran small tubing down inside casing. Washed out to 500'.
11-21-90	0 hours	Still couldn't get down past 550'. Ran tubing back in casing to 1300'. Washed out casing. Pulled tubing. Shot at 1200'. Came loose.

All open accounts are due by 10th of month following purchase. All amounts 30 days past due will be charged a FINANCE CHARGE at 1½% per month or an ANNUAL PERCENTAGE RATE of 18%.



# Donnelly Casing Pulling Co.

Phone 522-1410

P.O. Box 791  
Sterling, Colorado 80751

Bob Donnelly

**SOLD  
TO**

Sunset Hill  
c/o Mr. Mark Powell  
10442 North 75th St.  
Longmont, CO 80503

**INVOICE DATE** 12-13-90

**WELL**

Doll Estate #1

**INVOICE NO.** 91-109, page 2

DATE	DAY WORK	REMARKS
11-21-90	continued	Pulled joints.
11-27-90	0 hours	Pumped 20 sacks cement at 800'. Pulled casing, 30 total joints. Set 35 sacks cement in and out bottom of surface. Mudded to 35'. Set 10 sacks cement in top of surface. Cut off down 4'. Weld on cap.

WELL COMPLETE

THANK YOU

**RECEIVED**

FEB 28 1991

COLO. OIL & GAS CONS. COMM.