


RECEIVED

OCT - 6 1969



COLO. OIL & GAS CONS. COMM.  
OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO



SUNDRY NOTICES AND REPORTS ON WELLS

OIL & GAS  
CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplate	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to <del>Abandon Well</del> Plug-back	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Windsor Reservoir & Canal Co WELL NO. 1

FIELD New Windsor WILDCAT COUNTY Weld

LOCATION NE NE Section 34 Township 7N Range 67W Meridian 6th P.M.  
(Quarter Quarter)

968 feet from N Section Line and 662 feet from E Section Line  
N or S E or W

(DETAILS OF WORK)

Subject well was drilled to 9065' TD. The entire Lyons sand was penetrated plus 15' of the Lower Satanka. The Lyons had no permeability and no show. This is to confirm phone conversation of 6-21-57 between Mr. Rogers and O. L. Wyble, Lead Petroleum Engineer, in which approval for the following plug-back procedure was obtained:

- Plug #1 - 50 sacks slosset cement 8992'-8867' (Top of Lyons at 8986')
- Plug #2 - 50 sacks slosset cement 7672'-7547' (Top of Muddy at 7659')

Following this, it is planned to set 7" casing at  $\pm$  4400', and test the Sussex sand. Top of Sussex is 4272' ( $\pm$  678').

BEST IMAGE  
AVAILABLE

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED: 25  
JUN 24 1957

Date \_\_\_\_\_

Director [Signature]

Company The California Company Date 6-24-57

Address P. O. Box 1769, Casper, Wyo. Phone No. 2-5303

By [Signature] Title Area Supt.  
(Signature)