

FORM

2

Rev  
05/22

## State of Colorado

## Energy &amp; Carbon Management Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

403758045

(SUBMITTED)

Date Received:

05/16/2024

## APPLICATION FOR PERMIT TO

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and OperateAmend ☐TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: \_\_\_\_\_Refill ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: GRIMM MOTOCROSS 4-65

Well Number: 24-23 1AH

Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC

ECMC Operator Number: 10633

Address: 555 17TH STREET SUITE 3700

City: DENVER

State: CO

Zip: 80202

Contact Name: Jeff Annable

Phone: (303)312-8529

Fax: ( )

Email: jannable@civiresources.com

## FINANCIAL ASSURANCE FOR PLUGGING, ABANDONMENT, AND RECLAMATION

## ECMC Financial Assurance

☒ The Operator has provided or will provide Financial Assurance to the ECMC for this Well.

Surety ID Number (if applicable): 20160104

## Federal Financial Assurance

☐ In checking this box, the Operator certifies that it has provided or will provide at least this amount of Financial Assurance to the federal government for this Well. (Per Rule702.a.)

Amount of Federal Financial Assurance \$ \_\_\_\_\_

## WELL LOCATION INFORMATION

## Surface Location

QtrQtr: LOT 1 Sec: 19 Twp: 4S Rng: 64W Meridian: 6

FNL/FSL

FEL/FWL

Footage at Surface: 1301 Feet FNL 645 Feet FWL

Latitude: 39.692646

Longitude: -104.601089

GPS Data: GPS Quality Value: 1.3 Type of GPS Quality Value: PDOP

Date of Measurement: 12/03/2021

Ground Elevation: 5696

Field Name: DJ HORIZONTAL NIOBRARA

Field Number: 16950

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

## Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 24 Twp: 4S Rng: 65W

Footage at TPZ: 360 FNL 330 FEL

Measured Depth of TPZ: 8030

True Vertical Depth of TPZ: 7629 FNL/FSL FEL/FWL

**Base of Productive Zone (BPZ)**Sec: 23 Twp: 4S Rng: 65WFootage at BPZ: 360 FNL 330 FWLMeasured Depth of BPZ: 17929True Vertical Depth of BPZ: 7629 FNL/FSL FEL/FWL**Bottom Hole Location (BHL)**Sec: 23 Twp: 4S Rng: 65WFootage at BHL: 360 FNL 330 FWL

FNL/FSL FEL/FWL

**LOCAL GOVERNMENT PERMITTING INFORMATION**County: ARAPAHOEMunicipality: Aurora

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of §

24-65.1-108 C.R.S.? No

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I) (A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 07/19/2023Comments: The City of Aurora has approved the local application.**SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION**Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ IndianMineral Owner beneath this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Surface Owner Protection Bond (if applicable):

Surety ID Number (if applicable):

**MINERALS DEVELOPED BY WELL**

The ownership of all the minerals that will be developed by this Well is (check all that apply):

☒ Fee☐ State☒ Federal☐ Indian☐ N/A**LEASE INFORMATION**

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

\* If this Well is within a unit, describe a lease that will be developed by the Well.

\* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

Township 4 South Range 65 West  
Section 24: NE4Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease #

## SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 1714 Feet  
Building Unit: 4984 Feet  
Public Road: 631 Feet  
Above Ground Utility: 675 Feet  
Railroad: 5280 Feet  
Property Line: 645 Feet

### INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-1479	1221	T4SR65W: Sec 23-All except a part of the E2, Sect 24 - All

Federal or State Unit Name (if appl):

Unit Number:

## SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 330 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 690 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: Feet

## Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers.

## SPACING & FORMATIONS COMMENTS

## DRILLING PROGRAM

Proposed Total Measured Depth: 17929 Feet

TVD at Proposed Total Measured Depth 7629 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: \_\_\_\_\_ Feet ☒ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No If yes, attach an H<sub>2</sub>S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted? \_\_\_\_\_

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

**CASING PROGRAM**

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	A53B	36.95	0	80	105	80	0
SURF	13+1/2	9+5/8	J-55	36	0	3231	1315	3231	0
1ST	8+1/2	5+1/2	P-110	20	0	17929	2744	17929	0

☐ Conductor Casing is NOT planned

**POTENTIAL FLOW AND CONFINING FORMATIONS**

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Denver Aquifer	24	24	639	639	0-500	Groundwater Atlas	USGS HA-646 (Robson & Romero, 1981)
Groundwater	Arapahoe Aquifer	639	639	1246	1239	0-500	Groundwater Atlas	USGS HA-647 (Robson et al, 1981)
Groundwater	Laramie-Fox Hills	1246	1239	1973	1959	0-500	Groundwater Atlas	USGS HA-650 (Robson et al, 1981)
Confining Layer	Pierre Formation	1973	1959	2469	2449			
Groundwater	Upper Pierre Aquifer	2469	2449	3136	3109	1001-10000	Electric Log Calculation	WATKINS 30-5-8H (05-005-07189-0000)
Confining Layer	Base of Upper Pierre	3136	3109	4106	4069			
Hydrocarbon	Larimer-Parkman sandstone	4106	4069	4237	4199			Not productive in this area
Confining Layer	Pierre Formation	4237	4199	5319	5269			
Hydrocarbon	Terry-Sussex sandstone	5319	5269	5490	5439			Not productive in this area
Confining Layer	Pierre Formation	5490	5439	6228	6169			
Hydrocarbon	Hygiene-Shannon sandstone	6228	6169	6461	6399			Not productive in this area
Confining Layer	Pierre Formation	6461	6399	7659	7514			
Subsurface Hazard	Sharon Springs Member	7659	7514	8030	7629			Sloughing shales
Hydrocarbon	Niobrara Formation	8030	7629	17929	7629			

**OPERATOR COMMENTS AND SUBMITTAL**

## Comments

The distance to the completed portion of the nearest well in the same unit on the "Spacing & Formations" tab is measured to the proposed GRIMM MOTOCROSS 4-65 24 1B2BUH. This distance was measured in 2-dimensional space.

There are no wells belonging to another operator within 1500' of the proposed wellbore.

This wellbore will not be completed between the following portion of the wellbore to maintain setback to the spacing unit: Section 24, T4S, R645W (360FNL/370FWL) west to Section 23, T4S, R645W (360FNL/370FEL).

This application is in a Comprehensive Area Plan Yes

CAP #: 210700116

Oil and Gas Development Plan Name Lussing Trust North OGD

OGDP ID#: 485971

Location ID: 486500

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Jeff Annable

Title: Manager, Permitting

Date: 5/16/2024

Email: jannable@civiresources.com



Based on the information provided herein, this Application for Permit-to-Drill complies with ECMC Rules, applicable orders, and SB 19-181 and is hereby approved.

ECMC Approved: \_\_\_\_\_ Director of ECMC Date: \_\_\_\_\_  
Expiration Date: \_\_\_\_\_

API NUMBER

05

### **CONDITIONS OF APPROVAL, IF ANY LIST**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

#### **COA Type**

#### **Description**

0 COA

### **Best Management Practices**

#### **No BMP/COA Type**

#### **Description**

1	Drilling/Completion Operations	One of the first wells drilled on the pad during the first rig occupation will be logged with open-hole resistivity log with gamma-ray log from the kick-off point into the surface casing for one of the stratigraphically deepest wells on the pad. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs will state "Alternative Logging Program - No open-hole logs were run" and will clearly identify the type of log and the well (by API#) in which open-hole logs were run.
2	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.

Total: 2 comment(s)

### **ATTACHMENT LIST**

#### **Att Doc Num**

#### **Name**

403758226	WELL LOCATION PLAT
403758228	DEVIATED DRILLING PLAN
403761595	OffsetWellEvaluations Data
403793812	DIRECTIONAL DATA

Total Attach: 4 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Missing info on directional data excel sheet - operator #, API#, deviation indicator, north reference, grid type. Please upload a copy with said information. Uncheck the Federal mineral box as there are no federal minerals (only coal).	05/16/2024

Total: 1 comment(s)

