

Ranger Energy Services, LLC  
 10350 Richmond Avenue Suite 550  
 Houston, TX 77042  
 (713) 935-8900  
 (713) 935-8901 (FAX)



563075

Unit # C1002

Daily Work Ticket

Day #

<b>Customer Name</b>	<b>Customer AFE #</b>	<b>Date:</b>
Chevron	WBS:UWRWE-A2041- ABN Matt Morgan	6/19/2023

<b>Mailing Address</b>	<b>City</b>	<b>State</b>	<b>Zip</b>	<b>County</b>
	CO			Weld County, CO

<b>Field</b>	<b>Lease</b>	<b>Well</b>	<b>Order #</b>
		STATE A 41-16	
<b>TVD</b>	<b>MD</b>	<b>Calculated Horizontal Length</b>	<b>Company Rep</b>
00	00	0	Matt Morgan

<b>Work Description</b>	
P&A	<input checked="" type="checkbox"/>

<b>Sub Code Description</b>	
Cement	<input checked="" type="checkbox"/>

Description	Qty	Rate	Disc	Total	Stage
Turnkey PA Cement Pump Charge	1.00 @ \$0.00		0.00%	\$0.00	
Defoamer	1.00 @ \$0.00		0.00%	\$0.00	
Mud Flush	10.00 @ \$0.00		0.00%	\$0.00	
Cement (neat)	190.00 @ \$0.00		0.00%	\$0.00	
<b>TOTAL BILLABLE AMT</b>				<b>\$0.00</b>	

**Description of Work** Start Time 06:00 AM Stop Time 08:30 PM

From	To	Hours	Description	Details	Stage
6:00:41 AM	7:00:41 AM	1	RU/RD cement crew	C1002, MOB to location, Plug #1: 2-3/8" 4.7# at 2,177' stung into CICR in 4-1/2" 11.6#, perms at 2,277' - 1,777', pumped 5 fresh, 10	
7:00:41 AM	8:00:41 AM	1	RU/RD cement crew	mud flush, 5 fresh, 190 sxs or 38.9 bbl. of slurry, displaced 1.2 bbl. to inject 155 sxs, sting out, displace 5 bbl. to balance cement from	
8:00:41 AM	9:00:41 AM	1	RU/RD cement crew	2,277' - 1,714', RD valve, wash out, RDMO at 3:00 pm, Cement details: 15.8# 1.15 cu.ft./sack yield Class G cement, Water details: PH	
9:00:41 AM	10:00:41 AM	1	RU/RD cement crew	7.1 Chlorides <150 ppm, Temp: 69F, non rev: Pretrip and prep	

Payroll Section					
Employee	Rev Hours	Travel Hours	Non Rev Hours	Total	
Tool Pusher Garcia, Rodolfo F.	8.00	0.00	6.50	14.50	
Operator Chavez, Mirance B.	8.00	0.00	6.50	14.50	

**No Unreported Incidents Per My Signature**

\_\_\_\_\_  
 Ranger Representative

\_\_\_\_\_  
 Customer/Agent

Ranger Energy Services LLC and its customer acknowledge and agree that in the absence of an executed master service agreement, Ranger's Terms and Conditions will govern all services performed by Ranger including the allocation of liability for events occurring on location. A current copy may be obtained by email at Contracts@RangerEnergy.com or by calling 713.935.8906.