

FORM  
5A

Rev  
09/20

State of Colorado

Energy & Carbon Management Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:  
403553191

Date Received:  
02/16/2024

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. ECMC Operator Number: <u>10633</u>	4. Contact Name: <u>Elaine Winick</u>
2. Name of Operator: <u>CRESTONE PEAK RESOURCES OPERATING LLC</u>	Phone: <u>(303) 2947806</u>
3. Address: <u>555 17TH STREET SUITE 3700</u>	Fax: _____
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u>	Email: <u>ewinick@civiresources.com</u>

5. API Number <u>05-005-07517-00</u>	6. County: <u>ARAPAHOE</u>
7. Well Name: <u>Prosper Farms 4-65</u>	Well Number: <u>2-1-6 2AH</u>
8. Location: QtrQtr: <u>NWSW</u> Section: <u>2</u> Township: <u>4S</u> Range: <u>65W</u> Meridian: <u>6</u>	
9. Field Name: <u>DJ HORIZONTAL NIOBRARA</u> Field Code: <u>16950</u>	

## Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: HYDRAULIC FRACTURING

Treatment Date: 09/08/2023 End Date: 09/29/2023 Date this Formation was Completed: 01/20/2024

Perforations Top: 8800 Bottom: 23865 No. Holes: 3587 Hole size: 35/100 Open Hole:

Describe the Formation Treatment, including the following: type of fluid used (gel, slickwater, etc.), type and concentration of acid used (HCl, HF, etc.), types and amounts of proppant(s) used, depth details of multiple zones, and method used to determine flowback volume.

Frac'd Niobrara with 93 stage plug and perf:  
17481267 total pounds proppant pumped: 6707494 pounds 40/70 mesh; 10773773 pounds 100 mesh;  
751663 total bbls fluid pumped: 698582 bbls gelled fluid; 46414 bbls fresh water and 6667 bbls 15% HCl Acid.

This formation is commingled with another formation:  Yes  No

Total fluid used in treatment (bbl): 751663 Max pressure during treatment (psi): 9176

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.34

Type of gas used in treatment: \_\_\_\_\_ Min frac gradient (psi/ft): 0.81

Total acid used in treatment (bbl): 6667 Number of staged intervals: 93

Recycled or Reused Fluids used in treatment (bbl): 0 Flowback volume recovered (bbl): 0

Fresh water used in treatment (bbl): 46414 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 17481267

**Fracture stimulations must be reported on FracFocus.org**

### Test Information:

01/30/2024 Hours: 24 Bbl oil: 546 Mcf Gas: 574 Bbl H2O: 1418

Calculated 24 hour rate: Bbl oil: 546 Mcf Gas: 574 Bbl H2O: 1418 GOR: 1051

Test Method: FLOWING Casing PSI: 1143 Tubing PSI: 1376 Choke Size: 22/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1400 API Gravity Oil: 40

Tubing Size: 2 + 3/8 Tubing Setting Depth: 8189 Tbg setting date: 01/08/2024 Packer Depth: 8188

Reason for Non-Production: \_\_\_\_\_

Date formation Abandoned: \_\_\_\_\_ Squeeze:  Yes  No If yes, number of sacks cmt \_\_\_\_\_

\*\* Bridge Plug Depth: \_\_\_\_\_ \*\* Sacks cement on top: \_\_\_\_\_ \*\* Wireline and Cement Job Summary must be attached.

Comment:

TPZ 1850 FNL & 654 FWL

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Elaine Winick

Title: Completions Tech Date: 2/16/2024 Email ewinick@civiresources.com

### ATTACHMENT LIST

Att Doc Num	Name
403553191	FORM 5A SUBMITTED
403658379	WELLBORE DIAGRAM

Total Attach: 2 Files

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Passes Permitting	06/06/2024

Total: 1 comment(s)