



OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED
AUG 11 1960
OIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleat or abandon a well or to change plans. Within thirty (30) days after recompleat, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input checked="" type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME G. A. Henderson WELL NO. 6

FIELD Cedar Creek WILDCAT COUNTY Logan

LOCATION NE/4 NE/4 SW/4 ✓ Section 18 Township 9N Range 53W Meridian 6th PN
(Quarter Quarter)

2355 feet from South Section Line and 2645 feet from West Section Line
N or S E or W

(DETAILS OF WORK)

Before workover this well was producing 1 barrel oil and 36 barrels water per day from the 1st Dakota "D" Sand through casing perforations 4978'-4986'.

Squeezed off casing perforations 4978'-4986' with 150 sacks regular cement. Drilled cement out of 5 $\frac{1}{2}$ " OD casing and cleaned out to 5097'.

Perforated 5 $\frac{1}{2}$ " OD casing in 3rd Dakota "J" Sand 5089'-5094' with 20 shots. On July 21, 1960, treated these perforations with 200 gallons mud acid followed with 10,000# 20-40 sand and 10,000 gallons frac oil with 300# Dowell 4-12 gyp inhibitor.

After recovering all load oil, pumped 24 hours for 24 barrels new oil, no water, and 50,000 cubic feet gas. Date of recompletion was July 27, 1960.

AJJ	
DVR	
WRS	✓
HHM	
JAM	
FJP	
JJD	
FILE	

Not spaced for 5
330' from lease line
No prior approval

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Date _____
Director _____

Company Skelly Oil Company Date August 9, 1960
Address P. O. Box 310, Sterling, Colo. Phone No. LA 2-0289
By K. S. Lee Title Dist. Clerk
(Signature)

No approval prior to recompletion