



00240350

OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

Mary E. Hefley Lease

(Indicate nature of data by checking below)

- Notice of intention to drill.....
- Notice of intention to change plans.....
- Notice of date for test of water shut-off.....
- Report on result of test of water-shut-off.....
- Notice of intention to re-drill or repair well.....
- Notice of intention to clean out well.....
- Statement of shooting.....
- Statement of perforating.....
- Notice to pull or otherwise alter casing.....
- Notice of intention to abandon well.....
- Report of work done on well since previous report.....
- Report of setting oil string..... **X**

February 14 1947

Following is a (notice of intention to do work) (On land)
(report of work done) (patented) described as follows:

Colorado	Rio Blanco	Rangely
State	County	Field
Well No. <u>3 NE/4 - 2</u>	<u>1 N</u>	<u>102 W</u>
($\frac{1}{4}$ Sec.)	(Twp.)	(Range)
The Well is located <u>1086</u> ft. (N) of North	and <u>2740</u> ft. (E) of West	
	(S)	(W)

The elevation above sea level is 5216 (RDB) ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Landed 1744', 23#, J-55, 7" OD casing and 4016', 20# J-55, 7" OD casing at 5735' with 900 sax, 2-1-47. Temperature survey showed top cement behind casing at 3100. Tested casing with 500# pump pressure, held OK for 1 hour. W.O.C. 49 hours and drilled plug

Approved: Feb. 21 1947
W. Roy MacGinnis
State Oil Inspector

Company Stanolind Oil and Gas Company
Address Rangely, Colorado
By [Signature]
Title Field Superintendent

Submit reports of proposed work, for approval, on this form. In Duplicate.