



OFFICE OF STATE OIL INSPECTOR
 SUNDRY NOTICES AND REPORTS OF WELLS
 LOCATED ON PRIVATE LANDS

Mary E. Hefley Lease

(Indicate nature of data by checking below)

- Notice of intention to drill.....
- Notice of intention to change plans.....
- Notice of date for test of water shut-off.....
- Report on result of test of water-shut-off.....
- Notice of intention to re-drill or repair well.....
- Notice of intention to clean out well.....
- Statement of shooting.....
- Statement of perforating.....
- Notice to pull or otherwise alter casing.....
- Notice of intention to abandon well.....
- Report of work done on well since previous report.....
- Report of Setting Intermediate Casing..... X

January 2, 1947

Following is a (notice of intention to do work) (On land)
 (report of work done) (patented) described as follows:

Colorado	Rio Blanco	Rangely
State	County	Field
Well No. 3-NE/4 2	1N	102W
(1/4 Sec.)	(Twp.)	(Range)
		6th
		(Meridian)
The Well is located 1086	ft. (N)	of North and 2710
	(S)	ft. (E) of West
		(W)
line of Section 2		

The elevation above sea level is 5216 ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Cemented 605.39' of 32.3#, H-40, 8 RT, 9 5/8" casing at 603.39' with 250 sax on 12-16-46. Found top plug at 518' and tested pipe w/500# for 30 min. Held pressure O.K. Drilled plug and found 547' cement below pipe. Circulated mud between 13 3/8 and 9 5/8" casing. Set 15 sack calseal plug with top at 618'. Recemented pipe w/ 250 sax regular bulk cement. Cement circulated. W.O.C. 36 hrs. and drilled plug from 576-628'.

Approved: Jan 8 1947
W. Roy MacLennan
 State Oil Inspector

Company Stanolind Oil & Gas
 Address Rangely, Colorado
 By J. M. Doe
 Title Field Superintendent

Submit reports of proposed work, for approval, on this form. In Duplicate.