

FORM
5Rev
12/20

State of Colorado

Energy & Carbon Management Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

403896172

Date Received:

DRILLING COMPLETION REPORT

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

ECMC Operator Number: 10633

Contact Name: Kamrin Stiver

Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC

Phone: (303) 3128532

Address: 555 17TH STREET SUITE 3700

Fax:

City: DENVER State: CO Zip: 80202

Email: kstiver@civiresources.com

API Number 05-001-10566-00

County: ADAMS

Well Name: King 3-65

Well Number: 28-29 2BH

Location: QtrQtr: NESE Section: 28 Township: 3S Range: 65W Meridian: 6
FNL/FSL FEL/FWL

Footage at surface: Distance: 1778 feet Direction: FSL Distance: 435 feet Direction: FEL

As Drilled Latitude: 39.759380 As Drilled Longitude: -104.660995

GPS Data: GPS Quality Value: 1.6 Type of GPS Quality Value: PDOP Date of Measurement: 07/01/2024

** If directional footage at Top of Prod. Zone Dist: 2191 feet Direction: FNL Dist: 330 feet Direction: FEL
Sec: 28 Twp: 3S Rng: 65W** If directional footage at Bottom Hole Dist: 2173 feet Direction: FNL Dist: 343 feet Direction: FWL
Sec: 29 Twp: 3S Rng: 65W

Field Name: DJ HORIZONTAL NIOBRARA

Field Number: 16950

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 04/30/2024 Date TD: 05/21/2024 Date Casing Set or D&A: 05/22/2024

Rig Release Date: 06/23/2024 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 18346 TVD** 8013 Plug Back Total Depth MD 18336 TVD** 8013

Elevations GR 5585 KB 5610 Digital Copies of ALL Logs must be Attached ☒

List All Logs Run:

CBL, MWD, (RES 001-10564, 001-10568, 001-10558, 001-10562)

FLUID VOLUMES USED IN DRILLING OPERATIONS

(Enter "0" if a type of a fluid was not used. Do not leave blank.)

Total Fluids (bbls): 3869 Fresh Water (bbls): 1036

Recycled or Reused Fluids That Offset the Use of Fresh Water (bbls): 2339

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top	Status
CONDUCTOR	26	16	B	36.95	0	100	100	100	0	VISU
SURF	13+1/2	9+5/8	J55	36	0	3336	1383	3336	0	VISU
1ST	8+1/2	5+1/2	P110	20	0	18336	2910	18336	510	CBL

Bradenhead Pressure Action Threshold 1001 psig

This threshold is calculated per Rule 308A.b.(2)G. If this well is located in a bradenhead test area (see Rule 207.b) per an Order of the Commission, it may be subject to a different threshold.

Does the casing centralization comply with Rule 317.g? Yes

If "NO", provide details below.

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to ECMC)
	Top	Bottom	DST	Cored	
PARKMAN	4,986		NO	NO	
SUSSEX	5,357		NO	NO	
SHANNON	6,164		NO	NO	
SHARON SPRINGS	7,826		NO	NO	
NIOBRARA	7,895		NO	NO	

Operator Comments:

The TPZ footages are estimates calculated through Directional Plotting Software—from where the production string (5 ½" casing) crosses the 460' setback hardline. The actual footages will be submitted with the Form 5A.
Alternative Logging Program- No open hole resistivity log with gamma ray was run on this well per rule 317.p. A Resistivity log was run on King 3-65 28-29 1BH (001-10564), King 3-65 28-29 4BH (001-10568), Florida 3-65 27-26 1AH (001-10558), Florida 3-65 27-26 4BH (001-10562)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Kamrin StiverTitle: Drilling Technician

Date: _____

Email: kstiver@civiresources.com

ATTACHMENT LIST

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
403896216	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
403896209	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
403896195	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
403896197	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
403896198	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
403896203	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)