

US Treatment Report



Customer: CIVITAS RESOURCES

Rep:

Supervisor: JAMES RAGLE

Job Type: US Primary
Casing-Surface

Rig: Patterson 345

Well: Florida 03-65 27-26 01BH

UWI: Florida 03-65 27-26 01BH

Surface: Florida 03-65 27-26 01BH

Job #: JOB00181434

Job Date: 5-5-2024

Time Requested: 12:00PM

Time Arrived: 12:00PM

Time Released: 4:45PM

1408.3 sk MAG S 13.3 + 0.10% MCDF-P

Yield: 1.44 ft³/sk = 361.18bbls Mix Water: 7.01 gal/sk = 9872.18gal

BHCT (F)	100	BHST (F)	150	Casing Size (in)	9.625
Casing Grade	J-55	Casing Weight (lb/ft)	36	Casing Size (in)	9.625
Casing Grade	J-55	Casing Weight (lb/ft)	36	Float Depth (ft)	3357
Funnel Vis (sec/qt)	TBD	Max Pressure (psi)	1500	Mud Type	WBM
Plug Size (in)	9.625	Plug Type	Rig	TMD (ft)	3406
TVD (ft)	3285		Supplied		

Treatment Info: Sacks Used: 1408 Sacks Not Used: 0

Preflush: 5bbls Fresh Water & 10bbls MAG Mark & 10bbls Fresh Water

				Circulation Time:	1
		Slurry Temp:	72	Bulk Sample:	Yes
		Water Temp:	65	Water Sample:	Yes
		Bulk Temp:	70	Slurry Sample:	Yes
		Air Temp:	70	Air Pressure	29.5
Slurry Returns:	49	Plug Bumped:	Yes	Pump Out Lines:	No
Cement Class:		Type III		Humidity:	55
				Float Held:	Yes
				Precipitation:	0

Displace: 259.5bbls Fresh Water

Further Blend Details:

Prehydrated:

Additional Details (General Notes): CASING SET DEPTH 3396'

Time	Pressure psi	Annular Pressure psi	Volume Per Stage bbls	Total Stage Volume bbls	Rate bbls/mi n	Treatment Detail
12:00	0.00					Arrive on Location - GET NUMBERS FROM COMPANY MAN/ TEST ATER/ PH=8/ CHLORIDES=150/ HARDNESS=300
14:10	0.00					Safety Meeting - GO OVER JOB AND SAFETY WITH ALL PERSONNEL ON LOCATION
14:26	150.00			5	3	Fill Lines - FRESH WATER TO FILL LINES
14:29	2,500.00					Start Pressure Test
14:32	200.00			20	2.5	Pump Preflush - 10 BBLS MAG MARK/ 10 BBLS FRESH WATER
14:37	700.00			361.2	6.5	Pump Slurry - MIX AND PUMP 1408.30 SKS 13.3PPG/ 361.2 BBLS VERIFIED USING SCALES/ GOOD RETURNS
15:36	0.00					Stop Pumping
15:38	0.00					Drop Plug - DROP TOP PLUG WITNESSED BY COMPANY MAN
15:39	1,000.00			210	7	Displace - FRESH WATER/ TOTAL DISPL=259.5 BBLS / GOOD RETURNS/ 100 AWAY 550 PSI/ 150 AWAY 700 PSI/ 200 AWAY 1000 PSI/

16:10	850.00			49.5	4	Decrease Rate - SLOW RATE
16:21	1,450.00					Bump Plug - BUMPED PLUG / 49 BBLS CEMENT TO SURFACE
16:22	0.00					Check Floats - FLOATS HELD 1.5 BBL BACK TO PUMP
16:25	0.00					Wash Up Truck - WASH UP PUMP INTO CELLAR
16:45	0.00					Leave Location



Customer: CIVITAS

Date: 5-5-2024

Ticket: 181434

Location: FLORIDA 03-65 27-26 01BH

Well Name: FLORIDA 03-65 27-26 01BH

Job Type: SURFACE

Magnum Unit #: 1507

