

OIL AND GAS CONSERVATION COMMISSION RECEIVED

DEPARTMENT OF NATURAL RESOURCES OF THE STATE OF COLORADO



JUL 22 1974

File in duplicate for Patented and Federal lands.
File in triplicate for State lands.

COLD. OIL & GAS CON

5. LEASE DESIGNATION AND SERIAL NO.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

<p>1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> <u>WATER INJECTION WELL</u></p> <p>2. NAME OF OPERATOR <u>CHEVRON OIL CO, WESTERN DIVISION</u></p> <p>3. ADDRESS OF OPERATOR <u>RANGELY, COLORADO 81648</u></p> <p>4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface <u>1880' SNL; 2482' EWL OF SEC. 4, T1N, R102W</u> At proposed prod. zone <u>SE NW 6th PM</u></p> <p>14. PERMIT NO. _____</p>	<p>7. UNIT AGREEMENT NAME <u>RANGELY WEBER SAND</u></p> <p>8. FARM OR LEASE NAME <u>NEWTON ASSOCIATED</u></p> <p>9. WELL NO. <u>B-1</u></p> <p>10. FIELD AND POOL, OR WILDCAT <u>RANGELY WEBER SAND</u></p> <p>11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA <u>SEC. 4 T1N, R102W</u></p> <p>12. COUNTY <u>RIO BLANCO</u></p> <p>13. STATE <u>COLORADO</u></p>
<p>15. ELEVATIONS (Show whether DF, RT, GR, etc.) <u>DF - 5190</u></p>	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETION <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input checked="" type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) <input type="checkbox"/>	

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT <input type="checkbox"/>
(Other) <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work AFTER AUGUST 1, 1974

It is proposed to plug and abandon this well as follows:

1. Rig up.
2. This well has a CIBP set at 5650' and one set at 5615', each capped with 2 sacks cement.
3. Pump 150 sacks cement down the 7"-surface pipe annulus.
4. Lay a 30' cement plug in the top of the 7" casing.
5. Weld a plate over casing head and install marker.
6. Remove or bury cement pumping unit foundation and "dead men".
7. Clean up all loose pipe, fittings, debris, etc. from location.
8. Scarify non grassy areas and plant seed (8-10#/acre), avoid further disturbance of surface conditions.

DVR	
FJP	
HHM	
JAM	✓
JJD	✓
GCH	
CGM	

18. I hereby certify that the foregoing is true and correct.

SIGNED J.A. THOMPSONTITLE UNIT SUPT.DATE 7-19-74

(This space for Federal or State office use)

DIRECTOR

APPROVED BY M. Rogers
CONDITIONS OF APPROVAL, IF ANY:

TITLE C. W. & CONN. CORP.DATE JUL 24 1974