

OFFICE OF STATE OIL INSPECTOR  
SUNDRY NOTICES AND REPORTS OF WELLS  
LOCATED ON PRIVATE LANDS



02358302

Newton - Assoc. Unit "B" Lease.

(Indicate nature of data by checking below)

Notice of intention to drill.....X  
Notice of intention to change plans.....  
Notice of date for test of water shut-off.....  
Report on result of test of water-shut-off.....  
Notice of intention to re-drill or repair well.....  
Notice of intention to clean out well.....  
Statement of shooting.....  
Statement of perforating.....  
Notice to pull or otherwise alter casing.....  
Notice of intention to abandon well.....  
Report of work done on well since previous report.....

Following is a (notice of intention to do work) (On land) 4/4 19 47  
(report of work done) (patented) described as follows:

Colorado	Rio Blanco	Rangely
State	County	Field
Well No. 1 NW/4 (1/4 Sec.)	1N (Twp.)	102W (Range)
		6th. (Meridian)

The Well is located 1880 ft. (N) of North and 2482 ft. (E) of West  
Line Sec. 4 (S) (W)

The elevation above sea level is .....ft. to be determined later.

Details of Plan of Work: (State names of and expected depths to objective sands:  
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-  
ing points, and all other important proposed work.)

Drill well to test Weber Sand to approximate total depth of 6350'. Set approximately  
80' of 13-3/8" surface casing and circulate cement; 2300' of 9-5/8" intermediate  
casing cemented with 400 sacks; 5700' of 7" oil string on top of Weber Sand and  
cemented with 900 sacks. Run temperature Survey to locate top of cement behind casing.  
Produce through 2-1/2" E.V.E. tubing from open sand face 5695 to 6350'. Shoot with  
SNG as and if required.

Approved: 4/7/47  
John E. Brown  
State Oil Inspector

Company Stanolind Oil and Gas Co.  
Address Rangely, Colorado  
By J. H. Poe  
Title Field Superintendent

Submit reports of proposed work, for approval, on this form. In Duplicate.