

OFFICE OF STATE OIL INSPECTOR  
 SUNDRY NOTICES AND REPORTS OF WELLS  
 LOCATED ON PRIVATE LANDS



02358301

Newton-Associated Unit "B" Lease

(Indicate nature of data by checking below)

- Notice of intention to drill.....
- Notice of intention to change plans.....
- Notice of date for test of water shut-off.....
- Report on result of test of water-shut-off.....
- Notice of intention to re-drill or repair well.....
- Notice of intention to clean out well.....
- Statement of shooting.....
- Statement of perforating.....
- Notice to pull or otherwise alter casing.....
- Notice of intention to abandon well.....
- Report of work done on well since previous report.....

May 12 19 47

Following is a (notice of intention to do work) (On land)  
 (report of work done) (patented) described as follows:

Colorado	Rio Blanco	Rangely
State	County	Field
Well No. 1 NW/4 (Sec 4)	T1N	6th
(1/4 Sec.)	(Twp.)	(Meridian)
The Well is located 1880 ft.	(N) of North	and 2482 ft. (E) of West
Section line	(S)	(W)

The elevation above sea level is 5191 ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

On April 4, 1947 a notice of "Intention to Drill" was filed, which provided for 80' of 13 3/8" surface casing and 2300' of 9 5/8" intermediate casing. We have set 13 3/8" casing at 373.64' and cemented it to surface and do not plan to set 9 5/8" casing unless bad lost circulation zones are encountered. We plan to set 7" casing to the top of the Weber sand and cement it to a point above the Dakota sand.

Approved: 5-16-47

*John E. Brown*  
 State Oil Inspector

Company Stanolind Oil and Gas Company

Address Rangely, Colorado

By *J. M. [Signature]*

Title Field Superintendent

Submit reports of proposed work, for approval, on this form. In Duplicate.