



US Treatment Report

Customer: CIVITAS RESOURCES

Rep: Josh Kleison

Supervisor: ANTHONY GARCIA

Job Type: US Primary
Casing-Surface

Rig: Patterson 572

Well: JESSER East 03E-20-02

UWI: JESSER East 03E-20-02

Surface: JESSER East 03E-20-02

Job #: JOB00186366

Job Date Jul 03 @ 00:00

Time Requested: Jul 03 @ 09:00

Time Arrived: Jul 03 @ 18:00

Time Released: Jul 04 @ 00:30

711.4 sk MAG S 13.3 + 0.10% MCDF-P

Yield: 1.44 ft³/sk = 182.45bbls Mix Water: 7.01 gal/sk = 4986.91gal

BHCT (F)	92	BHST (F)	150	Surface Casing Size (in)	9.625
Surface Casing Grade	J-55	Surface Casing Weight (lb/ft)	36	Collapse Csg Pressure (psi)	2020
Float Depth (ft)	1636	Max Csg Pressure (psi)	3520	Max Pressure (psi)	1500
Mud Type	WBM	Plug Size (in)	9.625	Plug Type	Rig
TMD (ft)	1678	TVD (ft)	1612		Supplie d

Treatment Info: Sacks Used: 711.4 Sacks Not Used: 0

Preflush: 10bbls MAG Mark & 30bbls Fresh Water

Displace: 126.5bbls Fresh Water

Circulation Time: 1

Slurry Temp: 83 Bulk Sample: Yes

Water Temp: 74 Water Sample: Yes

Bulk Temp: 80 Slurry Sample: Yes

Air Temp: 81 Air Pressure 29.6

Slurry Returns: 30 Plug Bumped: Yes Pump Out Lines: Float Held: Yes

Cement Class: Type III Humidity: 15 Precipitation: 0

Further Blend Details:

Prehydrated:

Additional Details (General Notes):

Time	Pressure psi	Annular Pressure psi	Volume Per Stage bbls	Total Stage Volume bbls	Rate bbls/mi n	Treatment Detail
13:00	0.00					Arrive on Location - GET NUMBERS FROM COMPANY MAN, SPOT IN EQUIPMENT AND TEST WATER PH-8 CHLORIDES-100 HARDNESS-50
22:00	0.00					Safety Meeting - HELD SAFETY MEETING TO GO OVER SAFETY AND JOB PROCEDURES WITH RIG CREW, COMPANY MAN AND MAGNUM CREW
22:26	200.00			5	4.5	Fill Lines - FILL LINES 5 BBLS
22:30	2,600.00			0.5	.5	Start Pressure Test - TEST LINES TO 2600 PSI
22:33	250.00			40	6.5	Pump Preflush - 10 MAG MARK 30 BBLS FRESH WATER
22:42	300.00			182.4	6.5	Pump Slurry - MIX AND PUMP 711.4 SKS/182.4 BBLS OF MAG S 13.3 PPG VERIFIED WITH PRESSUREIZED SCALES
23:15	0.00					Stop Pumping

23:16	0.00					Drop Plug - DROP TOP PLUG WITNESSED BY COMPANY MAN
23:18	500.00			105	8	Displace - TOTAL DISPLACEMENT 126.5 BBLS
23:36	500.00			21.5	3	Decrease Rate - SLOWED TO BUMP PLUG
23:42	1,000.00					Bump Plug - 30 BBLS OF CEMENT TO SURFACE
23:52	0.00					Check Floats - HOLD PRESSURE FOR 10 MINUTES 1.5 BBL BACK FLOATS HELD
00:00	0.00					Wash Up Truck - WASH UP INTO CELLAR
00:30	0.00					Leave Location



Customer: CIVITAS

Date: June 3, 2024

Ticket: 186366

Location: JESSER EAST 03E-20-02

Well Name: JESSER EAST 03E-20-02

Job Type: SURFACE

Magnum Unit #: 1507

