

Anchor Testers, Inc.

GRAHAM, TEXAS

Test Ticket No. 6289

Order No. _____

Date 8/08/93

Company Egeria Oil Company Lease Sleeping Lion Well No. 12-2 Test No. 1

Field Wildcat County Routt State Colorado District Colo

Mail Charts To Middleton Investments, Inc. 1025 Dunn Road, Florissant, MO 63031

Mail Invoice To SAME

Formation Tested Frontier Total Depth 1373' Packer Depth 1338' Main Hole 7 7/8"
Interval Tested 1338' To 1373 Anchor Length 35' Rat Hole 7 7/8"
Drill Pipe 4 1/2" X Hole Drill Collars 4 1/2" H 90 Packer Type Bobtail Size 6 3/4 Number two
Time Packer Set _____ a.m. 8:45 p.m. _____ Packer Set 3 Hours 50 Minutes
Time Tool Open _____ a.m. 8:50 p.m. _____ Tool Open 2 Hours 05 Minutes
Initial Shut In _____ 45 Minutes Final Shut In 1 Hours _____ Minutes
Recorder Type AK-1 Capacity 6500 Number: Top 10281 Bottom 13431
Top Recorder Depth 1348' Bottom Recorder Depth 1373'
Top Clock Number 697 Bottom Clock Number 700
Four Stage Shut In Tool Yes X No _____ Maximum Temperature _____ Packer Hold Yes X No _____ Reversed Out Yes _____ No X
Mud Type Gel Mud Weight 8.9 Viscosity 60 Filter Cake 2/32 Water Loss 8.8
Choke Size - Top 3/4" Adj Bottom 5/8" Did Tool Plug? no Fluid Cushion no Kind none
Conventional Test yes Straddle Test no Casing Test no Miss Run no
Second Assembly yes Rotary Jar yes Safety Joint yes
Operator's Time _____ Tool Rental Time _____ Standby Time _____ Mileage _____
Surface Action Tool open with good blow, GTS in 2 minutes; reopen with good blow, decreased to weak blow.
Recovery 5' gas cut mud.

Remarks: 5 minute preflow.

Tester Bobby Rice

Test Approved By _____

		Recorder No.		Recorder No.		Recorder No.		Recorder No.
		10281						
A	Initial Hydrostatic Pressure	647	P.S.I.		P.S.I.		P.S.I.	P.S.I.
B	Initial Shut In Pressure	149	P.S.I.		P.S.I.		P.S.I.	P.S.I.
C	Initial Flow Pressure	33	P.S.I.		P.S.I.		P.S.I.	P.S.I.
D	Final Flow Pressure	33	P.S.I.		P.S.I.		P.S.I.	P.S.I.
E	Final Shut In Pressure	49	P.S.I.		P.S.I.		P.S.I.	P.S.I.
F	Final Hydrostatic Pressure	647	P.S.I.		P.S.I.		P.S.I.	P.S.I.
							P.S.I.	P.S.I.



00052444

TT# 6289

Top: 10281



TT# 6289

Bottom: 13431

