



<div>FORM</div> <div>6</div> <div>Rev 11/20</div>	<div>State of Colorado</div> <div>Energy &amp; Carbon Management Commission</div> <div>1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109</div>	<div></div>	<table><tr><td>DE</td><td>ET</td><td>OE</td><td>ES</td></tr></table>	DE	ET	OE	ES																													
	DE	ET	OE	ES																																
<div>WELL ABANDONMENT REPORT</div> <div><p>This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set. A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.</p></div>			<div>Replug By Other Operator</div> <div>Document Number: 403941593</div> <div>Date Received:</div>																																	
<div><div>ECMC Operator Number: 100322</div><div>Contact Name: Greg Deronde</div><div>Name of Operator: NOBLE ENERGY INC</div><div>Phone: (720) 315-2038</div><div>Address: 1099 18TH STREET SUITE 1500</div><div>Fax:</div><div>City: DENVER State: CO Zip: 80202</div><div>Email: greg.deronde@chevron.com</div><div>For "Intent" 24 hour notice required, Name: Burns, Adam Tel: (970) 218-4885</div><div>ECMC contact: Email: adam.m.burns@state.co.us</div></div>																																				
<div>Type of Well Abandonment Report: <input checked="" type="checkbox"/> Notice of Intent to Abandon <input type="checkbox"/> Subsequent Report of Abandonment</div>																																				
<div><div>API Number 05-123-05142-00</div><div>Well Name: STATE Well Number: 1</div><div>Location: QtrQtr: SENW Section: 16 Township: 4N Range: 63W Meridian: 6</div><div>County: WELD Federal, Indian or State Lease Number:</div><div>Field Name: WILDCAT Field Number: 99999</div></div>																																				
<div>Only Complete the Following Background Information for Intent to Abandon</div> <div><div>Latitude: 40.313777 Longitude: -104.445291</div><div>GPS Data: GPS Quality Value: 1.2 Type of GPS Quality Value: PDOP Date of Measurement: 02/19/2024</div><div>Reason for Abandonment: <input type="checkbox"/> Dry <input type="checkbox"/> Production Sub-economic <input type="checkbox"/> Mechanical Problems</div><div><input checked="" type="checkbox"/> Other re-enter to re-plug</div><div>Casing to be pulled: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Estimated Depth:</div><div>Fish in Hole: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No If yes, explain details below</div><div>Wellbore has Uncemented Casing leaks: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If yes, explain details below</div><div>Details: fish - 16 jts drill pipe 7356'-7885'</div></div>																																				
<div>Current and Previously Abandoned Zones</div> <table><tr><th>Formation</th><th>Perf. Top</th><th>Perf. Btm</th><th>Abandoned Date</th><th>Method of Isolation</th><th>Plug Depth</th></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td></tr></table> <div>Total: 0 zone(s)</div>				Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth																											
Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth																															
<div>Casing History</div> <table><tr><th>Casing Type</th><th>Size of Hole</th><th>Size of Casing</th><th>Grade</th><th>Wt/Ft</th><th>Csg/Liner Top</th><th>Setting Depth</th><th>Sacks Cmt</th><th>Cmt Btm</th><th>Cmt Top</th><th>Status</th></tr><tr><td>SURF</td><td>12+1/4</td><td>10+3/4</td><td>NA</td><td>32.75</td><td>0</td><td>425</td><td></td><td>425</td><td>0</td><td>VISU</td></tr><tr><td>OPEN HOLE</td><td>9+3/4</td><td></td><td></td><td></td><td></td><td>7885</td><td></td><td></td><td></td><td></td></tr></table>				Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top	Status	SURF	12+1/4	10+3/4	NA	32.75	0	425		425	0	VISU	OPEN HOLE	9+3/4					7885				
Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top	Status																										
SURF	12+1/4	10+3/4	NA	32.75	0	425		425	0	VISU																										
OPEN HOLE	9+3/4					7885																														

Date Run: 10/1/2024 Doc [#403941593] Well Name: STATE 1

Page 1 of 4

## Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #2: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #3: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #4: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #5: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set	238	sks cmt from	3500	ft. to	3000	ft.	Plug Type:	OPEN HOLE	Plug Tagged:	<input type="checkbox"/>
Set	143	sks cmt from	2300	ft. to	2000	ft.	Plug Type:	OPEN HOLE	Plug Tagged:	<input type="checkbox"/>
Set	305	sks cmt from	625	ft. to	0	ft.	Plug Type:	OPEN HOLE	Plug Tagged:	<input checked="" type="checkbox"/>
Set		sks cmt from		ft. to		ft.	Plug Type:		Plug Tagged:	<input type="checkbox"/>
Set		sks cmt from		ft. to		ft.	Plug Type:		Plug Tagged:	<input type="checkbox"/>

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth  
(Cast Iron Cement Retainer Depth)

Set \_\_\_\_\_ sacks half in. half out surface casing from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Tagged: ☐

Set \_\_\_\_\_ sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☐ No

Set \_\_\_\_\_ sacks in rat hole Set \_\_\_\_\_ sacks in mouse hole

### Additional Plugging Information for Subsequent Report Only

Casing Recovered: \_\_\_\_\_ ft. of \_\_\_\_\_ inch casing Number of Days from Setting Surface Plug  
Surface Plug Setting Date: \_\_\_\_\_ Cut and Cap Date: \_\_\_\_\_ to Capping or Sealing the Well: \_\_\_\_\_

\*Wireline Contractor: \_\_\_\_\_ \*Cementing Contractor: \_\_\_\_\_

Type of Cement and Additives Used: \_\_\_\_\_

Flowline/Pipeline has been abandoned per Rule 1105 ☐ Yes ☐ No

Technical Detail/Comments:

Purpose is to re-enter and adequately re-plug prior to hydraulic fracturing. A closed loop system will be used.

3rd party wildlife surveys will be conducted on this well prior to rigging up for P&A activities.

Notification will be given to any adjacent building unit occupants within a 1000 feet of the wellhead of planned P&A start date.

Please be aware that Form 6 Approval can predate actual rig work by up to several months and that environmental conditions can change quickly over that time. Chevron's Environmental Site Screening Process incorporates full environmental field clearances within 7 days of a scheduled well-work activity once the well is added to the active workover rig schedule. Should sensitive HPH conditions be identified during the screening process, Chevron will delay the work until conditions (nesting) clear and/or consult directly with CPW for guidance and discussion of potential mitigation measures that may be incorporated.

CPW consult not required.

**Procedure**

1 NU flange adaptor.

2 MIRU. Conduct pre-job safety meeting.

3 Complete a Form 17 Bradenhead Test.

4 Kill well with 8.3 ppg fresh water. Consult Engineer if unable to kill well with FW.

5 Verify well is static. Flow check well for 15 minutes. N/U 5K 9" BOP (or larger): 2.875" pipe rams and blind rams. Adapter will be needed from WH to BOP.

6 Pressure test BOP connection. Bleed pressure.

7 RU Power swivel

8 PU Drillout BHA (tri-cone bit, bit sub, drill collars, tubing).

9 RIH to TOC, mill to 400'. Pressure test surface casing against cement plug at 400' to 300 psi for 15 minutes 5% decrease allowed. This is to verify surface casing has integrity.

10 RIH and mill through surface shoe plug, est BOC is 430'.

11 RIH to 3500'

12 Circulate 2X bottoms up

13 POOH, L/D BHA

14 RIH to 3500' open ended.

15 Establish circulation. Pump 10bbbls Chemical Wash followed by 238 sks of cement, plug from 3500'-3000'. Displace with fresh water to balance plug.

16 POOH w/ tubing to 2900' and reverse circulate until clean returns observed.

17 POOH w/ tubing to 2300'.

18 Pump 10bbbls Chemical Wash followed by 143 sks of cement, plug from 2300'-2000'. Displace with fresh water to balance plug.

19 POOH w/ tubing to 1750' and reverse circulate until clean returns observed.

20 POOH w/ tubing to 625'.

21 Pump 305 sacks of cement to surface.

22 Top off cement if needed. Cement needs to be approx. 10' from surface.

23 ND BOP.

24 RDMO.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Sharon Strum

Title: Lead Wells Technical Asst

Date: \_\_\_\_\_

Email: sharon.strum@chevron.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with ECMC Rules and applicable orders and is hereby approved.

ECMC Approved: \_\_\_\_\_

Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY LIST**

Expiration Date: \_\_\_\_\_

**COA Type**

**Description**

0 COA	

**ATTACHMENT LIST**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
403941700	WELLBORE DIAGRAM
403941701	WELLBORE DIAGRAM
403941704	LOCATION PHOTO
403941714	SURFACE AGRMT/SURETY

Total Attach: 4 Files

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
		Stamp Upon Approval

Total: 0 comment(s)