



Customer Name	Customer AFE #	Date:	Stamp:
Chevron	UWRWE-A4169-ABN	08/20/2024	

State	County
CO	Weld County, CO

Well	Order #	
UPRC 35-5F		
Company Rep	Inter Company	LOB
Craig East		

Work Description	
P&A	✓

Sub Code Description	
Cement	✓

Description	Qty
Cement Service, Each Additional Hour	4.00
Gas Block Cement, Per Sack	102.00
Cement Rig Up & First 5 Hours	1.00
Cement Defoamer	1.00
Mud Flush	20.00
Calcium Chloride, Per Sack	2.00
Class "G" Cement, Per Sack	385.00

Description of Work	Start Time	Stop Time
	06:00 AM	

From	To	Hours	Description	Details
08/20/24 11:05:45 PM	08/21/24 12:05:45 AM	1	RU/RD cement crew	C1003, Plug1:2-3/8" 4.7# in 9" OH at 2371', 10bbls of Mudflush, 102 sxs
08/21/24 12:05:45 AM	08/21/24 01:05:45 AM	1	RU/RD cement crew	or 23.7 bbl slurry, then displaced 7.9bbls of fresh to balance from 2371'
08/21/24 01:05:45 AM	08/21/24 02:05:45 AM	1	RU/RD cement crew	to 2049'. RD valve, wash out, Cement details: 15.2# 1.31 cu.ft./sack
08/21/24 02:05:45 AM	08/21/24 03:05:45 AM	1	RU/RD cement crew	yield 2K thixo cement.
08/21/24 03:05:45 AM	08/21/24 04:05:45 AM	1	RU/RD cement crew	C1003, Plug2:2-3/8" 4.7# in 9" OH at 1431', 10bbls of Mudflush, 5bbl
08/21/24 04:05:45 AM	08/21/24 05:05:45 AM	1	RU/RD cement crew	fresh, 385 sxs or 78.8 bbl slurry, then displaced 1.6bbls of fresh to
08/21/24 05:05:45 AM	08/21/24 06:05:45 AM	1	RU/RD cement crew	balance from 1431' to 409'. RD valve, wash out, RDMO at 6:30 pm
08/21/24 06:05:45 AM	08/21/24 07:05:45 AM	1	RU/RD cement crew	Cement details: 15.8# 1.15 cu.ft./sack yield Great cement. Water
08/21/24 07:05:45 AM	08/21/24 08:05:45 AM	1	RU/RD cement crew	details: PH 7.1, Chlorides <50 ppm, Temp: 73F. C1003

Payroll Section					
Employee	Rev Hours	Travel Hours	Non Rev Hours	Total	
Tool Pusher	Horton, Jamar R.	10.00	0.00	5.00	15.00
Operator	Felix-Vasquez, Carlos A.	10.00	0.00	5.00	15.00
Derrick	Acevedo, Cesar M.	10.00	0.00	5.00	15.00

No Unreported Incidents Per My  
Signature

Ranger Energy Services, LLC  
10350 Richmond Avenue Suite 550  
Houston, TX 77042  
(713) 935-8900  
(713) 935-8901 (FAX)



698844

Unit # C1003

Daily Work Ticket

Day #

Customer Name

Customer AFE #

Date:

Stamp:

Chevron

UWRWE-A4169-ABN

8/21/2024

State

County

CO

Weld County, CO

Well

Order #

UPRC 35-5F

Company Rep

Inter Company

LOB

Craig East

Work Description

P&A

✓

Sub Code Description

Cement

✓

Description

NavNo

Qty

Cement Rig Up & First 5 Hours

05-001-0001

1.00 @

Class "G" Cement, Per Sack

05-050-0001

232.00

Cement Defoamer

05-050-0004

3.00 @

Mud Flush

05-050-0014

10.00

Cement Service, Each Additional Hour

05-001-0005

2.00 @

Description of Work

Start Time 07:00 AM

Stop Time 12:00 PM

From	To	Hours	Description	Details	Stage	eRig
08/21/24 07:00:25 AM	08/21/24 08:00:25 AM	1	RU/RD cement crew	C1003, Plug 1.2-3/8" 4.7# in 9" OH at 562', 8-5/8 24# at 516', 5bbls of		False
08/21/24 08:00:25 AM	08/21/24 09:00:25 AM	1	RU/RD cement crew	Mudflush, 5bbl fresh, 227 sxs or 46.4 bbl slurry, to surface, topped of		False
08/21/24 09:00:25 AM	08/21/24 10:00:25 AM	1	RU/RD cement crew	with 5sx or 1bbl of slurry. RD valve, wash out, RDMO at 11:30 am		False
08/21/24 10:00:25 AM	08/21/24 11:00:25 AM	1	RU/RD cement crew	Cement details: 15.8# 1.15 cu.ft./sack yield Gneat cement. Water		False
08/21/24 10:00:25 AM	08/21/24 12:00:25 PM	2	RU/RD cement crew	details: PH 7.1, Chlorides <50 ppm, Temp: 73F. C1003		False

Payroll Section

Employee

Rev Hours

Travel Hours

Non Rev Hours

Total

Tool Pusher	Horton, Jamar R.	7.00	0.00	1.00	8.00
Operator	Felix-Vasquez, Carlos A.	7.00	0.00	1.00	8.00
Derrick	Acevedo, Cesar M.	7.00	0.00	1.00	8.00

No Unreported Incidents Per My  
Signature

Ranger Representative

Customer/Agent

Ranger Energy Services LLC and its customer acknowledge and agree that in the absence of an executed master service agreement, Ranger's Terms and Conditions will govern all services performed by Ranger including the allocation of liability for events occurring on location. A current copy may be obtained by email at [Contracts@RangerEnergy.com](mailto:Contracts@RangerEnergy.com) or by calling 713.935.8906.