



Revegetation/Reclamation
Rangeland Rehabilitation
Fencing
Hydroseeding
Environmental Consulting

ROCKY MOUNTAIN RECLAMATION

Phone (307) 745-5235
Fax (307) 745-5230

eric@reveg.us
www.reveg.us

P.O. Box 1695
Laramie, WY 82073

RECLAMATION PLAN FOR THE APTIM & MULL DRILLING TANK SITE PECK TANK BATTERY

RECLAMATION PLAN

Introduction

APTIM and Mull Drilling plan to restore the site known as Peck Tank Battery. The sites will be reclaimed in the following manner.

Procedures

Soil samples have been obtained and reclamation procedures are based on the obtained samples. There are areas of high pH so the entire site will be treated in the following manner.

Decompaction: The site will be ripped 8"-12" deep and prepared for soil amendments.

Application of Soil Amendments: 6,000 lbs/acre of pelletized gypsum, 1,000 lbs/acre of elemental sulfur, 200 lbs/acre of Humic Acid, and 100 lbs/acre of mycorrhizal fungi.

Application of Fertilizer: 2,000 lbs/acre of Sustane 4-6-4 slow release organic fertilizer.

Incorporation and Seedbed Preparation: Incorporation of soil amendments and seedbed preparation will include scarifying and/or disking as necessary to prepare a proper seedbed for the native species in a NRCS approved seed mixture.

Rangeland Drill Seeding: The disturbed areas will be reseeded by the landowner for use as cropland.