

Ranger Energy Services, LLC
10350 Richmond Avenue Suite 550
Houston, TX 77042
(713) 935-8900
(713) 935-8901 (FAX)



704683

Unit # R5003

Daily Work Ticket

Day # 2

Customer Name

Chevron

Customer AFE #

Date:

8/28/2024

Stamp:

State

County

CO

Weld County, CO

Well

Order #

BOULTER G14-24

Company Rep

Inter Company

LOB

MATT MORGAN

Work Description

P&A

✓

Sub Code Description

Tubing

✓

Description

NavNo

Qty

Rate

Disc

Total

Notes

TOTAL BILLABLE AMT \$0.00

Description of Work

Start Time 06:00 AM

Stop Time 04:00 PM

From	To	Hours	Description	Details	Stage	eRig
08/28/24 06:00:00 AM	08/28/24 06:30:00 AM	0.5	Travel to/from location	TRAVEL TO LOCATION.		False
08/28/24 06:30:00 AM	08/28/24 07:00:00 AM	0.5	Review SOP's/Complete JSA	REVIEW JSA PERFORM SAFETY MEETING.		False
08/28/24 07:00:00 AM	08/28/24 07:30:00 AM	0.5	Check or bleed down pressure from wellhead / tubing / casing	PSI 00/00. PERFORM DAILY EQUIPMENT INSPECTION.		False
08/28/24 07:30:00 AM	08/28/24 09:30:00 AM	2	RU to pull / run rods or tubing	POOH SB ON DERRICK 76 JOINTS LD 108 JOINTS 2 3/8 4.7 TBG.		False
08/28/24 09:30:00 AM	08/28/24 10:30:00 AM	1	RU/RD/run wireline/slickline	SAFETY MEETING MIRU WL.		False
08/28/24 10:30:00 AM	08/28/24 11:30:00 AM	1	RU/RD/run wireline/slickline	RIH W/4" CIBP @4,019'. POO W.SETTING TOOL. RIH W/DB + 2 SKS CMT. POOH.		False
08/28/24 11:30:00 AM	08/28/24 12:00:00 PM	0.5	RU/RD/run wireline/slickline	RIH W/4" CIBP @2,336'. POOH W/SETTING TOOL .		False
08/28/24 12:00:00 PM	08/28/24 12:30:00 PM	0.5	RU/RD/run wireline/slickline	RIH W/6 SPF GUN. PRESSURE CSG 550 SPI. PERFORATE CSG @936'. GOOD PRESSURE DROP. POOH RDOM WL.		False
08/28/24 12:30:00 PM	08/28/24 01:00:00 PM	0.5	Customer Procedure Changes	BLOW OUT/DRILL PAD PERFORMED BY CVR REP.		False
08/28/24 01:00:00 PM	08/28/24 02:00:00 PM	1	Circulate fluid	CC 150 BBL FROM WORK TANK CONDITONE SF.		False
08/28/24 02:00:00 PM	08/28/24 03:00:00 PM	1	RIH/POOH with tubing	RIH W/TBG76 JOINTS TAG CIBP. SPACE OUT.		False
08/28/24 03:00:00 PM	08/28/24 03:30:00 PM	0.5	Shut in / lock out well	SECURE WH AND LOCATION. DEBRIEF.		False
08/28/24 03:30:00 PM	08/28/24 04:00:00 PM	0.5	Travel to/from location	TRAVEL FROM LOCATION.		False

Payroll Section

Employee		Rev Hours	Travel Hours	Non Rev Hours	Total
Tool Pusher	Rudd, Eric M.	9.00	1.00	0.00	10.00
Operator	Rubio Contreras, Daniel	9.00	1.00	0.00	10.00
Derrick	Ruiz Quezada, Manuel	9.00	1.00	0.00	10.00
FloorHand	Chavez, Erick E.	9.00	1.00	0.00	10.00
FloorHand	Rascon, Sergio	9.00	1.00	0.00	10.00

Ranger Energy Services, LLC
10350 Richmond Avenue Suite 550
Houston, TX 77042
(713) 935-8900
(713) 935-8901 (FAX)



704684

Unit # R5003

Daily Work Ticket

Day # 3

Customer Name

Customer AFE #

Date:

Stamp:

Chevron

8/29/2024

State

County

CO

Weld County, CO

Well

Order #

BOULTER G14-24

Company Rep

Inter Company

LOB

CHRIS E.

Work Description

P&A

✓

Sub Code Description

Tubing

✓

Description

NavNo

Qty

Rate

Disc

Total

Notes

TOTAL BILLABLE AMT \$0.00

Description of Work Start Time 06:00 AM Stop Time 02:00 PM

From	To	Hours	Description	Details	Stage	eRig
08/29/24 06:00:00 AM	08/29/24 06:30:00 AM	0.5	Travel to/from location	TRAVEL TO LOCATION.		False
08/29/24 06:30:00 AM	08/29/24 07:00:00 AM	0.5	Review SOP's/Complete JSA	REVIEW JSA PERFORM SAFETY MEETING.		False
08/29/24 07:00:00 AM	08/29/24 08:00:00 AM	1	Check or bleed down pressure from wellhead / tubing / casing	PSI 00/ PERFORM DAILY EQUIPMENT INSPECTION.		False
08/29/24 08:00:00 AM	08/29/24 09:00:00 AM	1	Spot Equipment	MIRU CMT. RIH TAG CIBP @ 2,336' THEN TOP 10 SKS CMT.		False
08/29/24 09:00:00 AM	08/29/24 11:00:00 AM	2	RU/RD cement crew	PUMP CEMENT @ 936 THRU CSG UP TO SF. WAIT 30 MIN THEN TOP OFF. PUMPED A TOTAL FO 288 SKS.		False
08/29/24 11:00:00 AM	08/29/24 12:00:00 PM	1	ND BOP stack / NU Wellhead	ND BOP, NU MASTER VALVE. WASH OUT EQUIPMENT.		False
08/29/24 12:00:00 PM	08/29/24 01:30:00 PM	1.5	RU/RD rig	RIG DOWN RIG AND HARD LINE CLEAN UP LOCATION.		False
08/29/24 01:30:00 PM	08/29/24 02:00:00 PM	0.5	Prep for rig move	GET EQUIPMENT READY FOR RIG MOVE. PERFORM PRE-TRIP INSPECTION.		False

Payroll Section

	Employee	Rev Hours	Travel Hours	Non Rev Hours	Total
Tool Pusher	Rudd, Eric M.	7.50	0.50	0.00	8.00
Operator	Rubio Contreras, Daniel	7.50	0.50	0.00	8.00
Derrick	Ruiz Quezada, Manuel	7.50	0.50	0.00	8.00
FloorHand	Chavez, Erick E.	7.50	0.50	0.00	8.00
FloorHand	Rascon, Sergio	7.50	0.50	0.00	8.00

No Unreported Incidents Per My Signature

Ranger Representative

Customer/Agent

Ranger Energy Services LLC and its customer acknowledge and agree that in the absence of an executed master service agreement, Ranger's Terms and Conditions will govern all services performed by Ranger including the allocation of liability for events occurring on location. A current copy may be obtained by email at Contracts@RangerEnergy.com or by calling 713.935.8906.

Ranger Energy Services, LLC
10350 Richmond Avenue Suite 550
Houston, TX 77042
(713) 935-8900
(713) 935-8901 (FAX)



701392

Unit # C1003

Daily Work Ticket

Day #

Customer Name

Chevron

Customer AFE #

UWRWE-A4150-ABN

Date:

8/29/2024

Stamp:

State

County

CO

Weld County, CO

Well

Order #

BOULTER G14-24

Company Rep

Inter Company

LOB

Chris Eberle

Work Description

P&A

✓

Sub Code Description

Cement

✓

Description

NavNo

Qty

Rate

Disc

Total

Notes

Cement Rig Up & First 5 Hours

Class "G" Cement, Per Sack

Calcium Chloride, Per Sack

Cement Defoamer

Mud Flush

Cement Service, Each Additional Hour

Description of Work

Start Time 07:00 AM

Stop Time 03:00 PM

From	To	Hours	Description	Details	Stage	eRig
08/29/24 07:00:00 AM	08/29/24 08:00:00 AM	1	RU/RD cement crew	C1003, Plug1:2-3/8 4.7# in 4-1/5 11.6# at 2336', 5bbls of fresh, 10 sxs or 2.04 bbl.		False
08/29/24 08:00:00 AM	08/29/24 09:00:00 AM	1	RU/RD cement crew	slurry, displaced 8.5bbl to balance from 2,336' to 2,203'. Cement details: 15.8# 1.15 cu.ft./sack yield Gneat cement.		False
08/29/24 09:00:00 AM	08/29/24 10:00:00 AM	1	RU/RD cement crew			False
08/29/24 10:00:00 AM	08/29/24 11:00:00 AM	1	RU/RD cement crew	C1003, Plug2:4-1/2" 11.6# in 9" OH at 936' 8-5/8" 24# at 736', 10bbls mud flush,		False
08/29/24 10:00:00 AM	08/29/24 11:00:00 AM	1	RU/RD cement crew	5bbls of fresh, 278 sxs or 56.9 bbl slurry to surface, topped of with 10sx or 2bbls.		False
08/29/24 11:00:00 AM	08/29/24 12:00:00 PM	1	RU/RD cement crew	RD valve, wash out, RDMO at 11:00 am Cement details: 15.8# 1.15 cu.ft./sack		False
08/29/24 12:00:00 PM	08/29/24 01:00:00 PM	1	RU/RD cement crew	yield Gneat cement. Water details: PH 7.1, Chlorides <50 ppm, Temp: 83F. C1003		False

Payroll Section

Employee	Rev Hours	Travel Hours	Non Rev Hours	Total
Tool Pusher Horton, Jamar R.	6.00	0.00	6.00	12.00
Operator Felix-Vasquez, Carlos A.	6.00	0.00	5.00	11.00
Derrick Acevedo, Cesar M.	6.00	0.00	5.00	11.00

No Unreported Incidents Per My Signature