

FORM  
5A

Rev  
09/20

State of Colorado

Energy & Carbon Management Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

403914433

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. ECMC Operator Number: 10633

2. Name of Operator: CRESTONE PEAK RESOURCES OPERATING LLC

3. Address: 555 17TH STREET SUITE 3700

City: DENVER State: CO Zip: 80202

4. Contact Name: Elaine Winick

Phone: (303) 2947806

Fax:

Email: ewinick@civiresources.com

5. API Number 05-001-10559-00

7. Well Name: Florida 3-65

8. Location: QtrQtr: NESE Section: 28 Township: 3S Range: 65W Meridian: 6

9. Field Name: DJ HORIZONTAL NIOBRARA Field Code: 16950

6. County: ADAMS

Well Number: 27-26 1BH

## Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: HYDRAULIC FRACTURING  
Treatment Date: 08/10/2024 End Date: 08/24/2024 Date this Formation was Completed: 10/15/2024  
Perforations Top: 8528 Bottom: 18408 No. Holes: 2285 Hole size: 35/100 Open Hole: ☐

Describe the Formation Treatment, including the following: type of fluid used (gel, slickwater, etc.), type and concentration of acid used (HCl, HF, etc.), types and amounts of proppant(s) used, depth details of multiple zones, and method used to determine flowback volume.

Niobrara Frac'd with 54 stage plug and perf:  
11514634 total pounds proppant pumped: 3437669 pounds 40/70 mesh; 8076965 pounds 100 mesh;  
471447 total bbls fluid pumped: 445121 bbls gelled fluid; 22445 bbls fresh water and 3881 bbls 15% HCl Acid.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 471447 Max pressure during treatment (psi): 8739  
Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.34  
Type of gas used in treatment: \_\_\_\_\_ Min frac gradient (psi/ft): 0.91  
Total acid used in treatment (bbl): 3881 Number of staged intervals: 54  
Recycled or Reused Fluids used in treatment (bbl): 0 Flowback volume recovered (bbl): 0  
Fresh water used in treatment (bbl): 22445 Disposition method for flowback: DISPOSAL  
Total proppant used (lbs): 11514634

**Fracture stimulations must be reported on FracFocus.org**

### Test Information:

10/25/2024 Hours: 24 Bbl oil: 690 Mcf Gas: 653 Bbl H2O: 392  
Date Calculated 24 hour rate: Bbl oil: 690 Mcf Gas: 653 Bbl H2O: 392 GOR: 946  
Test Method: flowing Casing PSI: 331 Tubing PSI: 917 Choke Size: 30/64  
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1300 API Gravity Oil: 40  
Tubing Size: 2 + 3/8 Tubing Setting Depth: 8099 Tbg setting date: 10/06/2024 Packer Depth: 8098  
Reason for Non-Production: \_\_\_\_\_  
Date formation Abandoned: \_\_\_\_\_ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt \_\_\_\_\_  
\*\* Bridge Plug Depth: \_\_\_\_\_ \*\* Sacks cement on top: \_\_\_\_\_ \*\* Wireline and Cement Job Summary must be attached.

Comment:

TPZ 1249 FNL & 345 FWL

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Elaine Winick  
Title: COMPLETIONS TECH Date: \_\_\_\_\_ Email: ewinick@civiresources.com  
:

### ATTACHMENT LIST

**Att Doc Num** **Name**

403982938 WELBORE DIAGRAM

Total Attach: 1 Files

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
		Stamp Upon Approval

Total: 0 comment(s)