

0503795

FORM NO.
GWS-31
10/94

WELL CONSTRUCTION AND TEST REPORT

STATE OF COLORADO, OFFICE OF THE STATE ENGINEER
1313 Sherman St., Rm 818, Denver, CO 80203

For Office Use only

RECEIVED

NOV 16 2001

WALLACE
STATE ENGINEER
COLO.1. WELL PERMIT NUMBER 234153-247461

2. OWNER NAME(S) Jay + Angela White
 Mailing Address 300 S. Padline Ave.
 City, St. Zip Milliken CO 80543
 Phone (970) 396-2376

0476755

KRM

3. WELL LOCATION AS DRILLED: SW 1/4 SE 1/4, Sec. 18 Twp. 4 N, Range 64 W

DISTANCES FROM SEC. LINES:

150 ft. from South Sec. line. and 2845 ft. from West Sec. line. OR
 (north or south) (east or west)

SUBDIVISION:

LOT

BLOCK

FILING(UNIT)

STREET ADDRESS AT WELL LOCATION:

4. GROUND SURFACE ELEVATION _____ ft. DRILLING METHOD Air rotary
 DATE COMPLETED 7-26-01 TOTAL DEPTH 240 ft. DEPTH COMPLETED 240 ft.

5. GEOLOGIC LOG:

Depth Description of Material (Type, Size, Color, Water Location)

0'-2' Topsoil.

2'-10' Sand.

10'-70' Clay.

70'-180' Shale.

180'-190' Sand.

190'-210' Shale.

210'-215' Sand.

215'-225' Shale.

225'-235' Sand.

235'-240' Shale.

24 GPM @ 200'

REMARKS:

6. HOLE DIAM. (in.) From (ft) To (ft)

8 1/8	0	40
6 7/8	40	240

7. PLAIN CASING

OD (in)	Kind	Wall Size	From (ft)	To (ft)
6 5/8	Steel	1.88	+2	40
4	PVC	Sch. 40	10	200

PERF. CASING: Screen Slot Size: .032 by V4
 4 PVC Sch. 40 200 240

8. FILTER PACK:

Material Silica Sand
 Size 8-12
 Interval 180'-240'

9. PACKER PLACEMENT:

Type _____
 Depth _____

10. GROUTING RECORD:

Material	Amount	Density	Interval	Placement
Portland Cement	4 bags	15#	7'-40'	Trimmie

11. DISINFECTION: Type Chlorine Amt. Used 3 cups12. WELL TEST DATA: ☐ Check box if Test Data is submitted on Form No. GWS 39 Supplemental Well Test.

TESTING METHOD

Static Level 40 ft. Date/Time measured 7-26-01 5:00pm Production Rate 24 gpm.Pumping level 240 ft. Date/Time measured 7-26-01 1:00pm Test length (hrs.) 2

Remarks

13. I have read the statements made herein and know the contents thereof, and that they are true to my knowledge. [Pursuant to Section 24-4-104 (13)(a) C.R.S., the making of false statements herein constitutes perjury in the second degree and is punishable as a class 1 misdemeanor.]

CONTRACTOR Bobby J. WallacePhone 307.635-7492 Lic. No. 1324Mailing Address P.O. Box 20985 Cheyenne, WY 82003

Name/Title (Please type or print)

Bobby J. Wallace

Signature

Bobby J. Wallace

Date

9-27-01